



ATTACHMENT 12-B



NOISE MONITORING NOTES:

- 1. CONTRACTOR SHALL MONITOR AND DOCUMENT BASELINE NOISE LEVELS AT THREE (3) OR MORE LOCATIONS NEAR THE IDENTIFIED RECEPTOR LOCATIONS DURING NON-WORKING PERIODS.
- 2. CONTRACTOR SHALL MONITOR AND DOCUMENT NOISE LEVELS AT THE SAME RECEPTOR LOCATIONS DURING THE PEAK ACTIVITY PERIOD.
- 3. CONTRACTOR SHALL USE A TYPE 2 / CLASS 2 SOUND LEVEL METER THAT MEETS OR EXCEEDS IEC 61672.

MATCH LINE - SEE THIS SHEET



NOISE GENERATION AND IMPACTS																						
PHASE	ACTIVITY	DAY	NIGHT	EQUIPMENT	QUANTITY	ACOUSTICAL USE FACTOR (%) *	WORK DESCRIPTION	RECEPTOR *	DISTANCE TO RECEPTOR (ft)	COMBINED CALCULATED (dBA) *		LIMITS (dBA) (Day) *		LIMITS (dBA) (Night) *		SHIELDING (dba) *	COMBINED CALCULATED EXCEEDANCE (dBA) *		NOTES / ACTIONS			
										Lmax	L10	Lmax	L10	Lmax	L10		Day	Night				
0	Construction Entrance	Yes	No	Dump Truck	5	40%	Delivery and removal of materials.	Residential homes	30	77.9	76.9	85	75	80	35	3	1.9	N/A	Exceedance is minimal. Receptor is the residential property that fronts Providence Road, therefore anticipated Daytime Baseline is likely to be at or exceeding the calculated noise level.			
1	Excavation	Yes	No	Excavator	2	40%	Waterline installation along eastern property boundary	Residential homes	300	77.9	78.6	85	75	80	35	3.0	3.6	N/A	No actions required			
1	Excavation	Yes	No	Off-Road Dump Truck	3	40%	Waterline installation along eastern property boundary	Residential homes	135													
1	Excavation	Yes	No	Dozer	1	40%	Maintenance of stockpile and site.	Residential homes	135													
1	Dewatering	Yes	Yes	Pumps (Per dba required)	2	100%	Dewatering of tank excavation.	Residential homes	500													
2	Pile Driving	Yes	No	Pile Driver Impact	1	20%	Pile Driving for tank foundation	Residential homes	530	77.8	73.8	85	75	80	35	3	No Exceedance	N/A	No actions required			
2	Pile Driving	Yes	No	Use Crane, Derrick	1	16%	Crane for pile driving	Residential homes	480									N/A				
										57.9	57.9	85	75	80	35	3.0	No Exceedance	22.9	Exceedance is minimal. Consider application of an Acoustic Shadow/Barrier such as straw bales or other. Combine with receptor perimeter monitoring.			
2	Dewatering	Yes	Yes	Pumps (Per dba required)	2	100%	Dewatering of tank excavation.	Residential homes	500													
3	Utility Installation	Yes	No	Backhoe	1	40%	Waterline installation along eastern property boundary	Residential homes	30	79.0	78.0	85	75	80	35	3.0	3.0	N/A	Exceedance is minimal. Possible additional shielding will occur via existing vegetation and stockpile storage area. Install receptor perimeter monitoring and potential remediation of proximity related equipment.			
3	Utility Installation	Yes	No	Compactor	1	40%	Waterline installation along eastern property boundary	Residential homes	30	84.7	80.7	85	75	80	35	3.0	5.7	N/A				
3	Utility Installation	Yes	No	Loader	1	40%	Waterline installation along eastern property boundary	Residential homes	30	80.5	79.6	85	75	80	35	3.0	4.6	N/A				
3	Tank Construction	Yes	No	Use Crane, Derrick	2	16%	Tank construction consisting of concrete placement and precast element placement.	Residential homes	480	60.4	61.4	85	75	80	35	3.0	No Exceedance	N/A				
3	Tank Construction	Yes	No	Concrete Mixers	2	15%		Residential homes	480													
3	Tank Construction	Yes	No	Concrete Vibrator	1	15%	Cast in place concrete placement.	Residential homes	480													
3	Tank Construction	Yes	No	Air Compressor	1	15%	For use near tank.	Residential homes	480													
3	Tank Construction	Yes	No	Loader	1	40%	For use on site-wide soil and material placement.	Residential homes	480													
4	Backfill & Final Grading	Yes	No	Excavator	1	40%	Backfilling of excavated areas and site-wide grading.	Residential homes	135	69.1	71.7	85	75	80	35	3.0	No Exceedance	N/A	No actions required			
4	Backfill & Final Grading	Yes	No	Off-Road Dump Truck	2	40%	Backfilling of excavated areas and site-wide grading.	Residential homes	135													
4	Backfill & Final Grading	Yes	No	Roller	1	40%	Backfilling of excavated areas and site-wide grading.	Residential homes	250													
4	Backfill & Final Grading	Yes	No	Grader	1	40%	Backfilling of excavated areas and site-wide grading.	Residential homes	250													
4	Backfill & Final Grading	Yes	No	Paver	1	40%	Paving of Barco Drive	Residential homes	40	76.2	76.1	85	75	80	35	3.0	1.1	N/A	Exceedance is minimal. No actions required.			
* NOTE: All calculations and noise data were developed using the Roadway Construction Noise Model (RCNM) developed by the Federal Highway Administration (FHWA), Version 1.1, 12/08/2008																						

SCALE: 1" = 60'



PROJECT ENGINEER:	T. McPHERSON
DESIGNED BY:	T. McPHERSON / C. LINK
DRAWN BY:	M. BRANDT
CHECKED BY:	T. McPHERSON
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO FULL SCALE	0 1/2" 1"
REV	ISSUED FOR
DATE	BY



HAZEN AND SAWYER
4500 MAIN STREET, SUITE 500
VIRGINIA BEACH, VIRGINIA 23462
PHONE: 757-497-0490



CROWDER CONSTRUCTION COMPANY
11111 BURMA DRIVE
APEX, NORTH CAROLINA 27539
PHONE: 800-849-5449




PROVIDENCE ROAD OFF-LINE
STORAGE FACILITY AND WOODSTOCK
PARK IMPROVEMENTS

PRECONSTRUCTION ASSESSMENT
AND DAMAGE MITIGATION PLAN
NOISE GENERATION AND IMPACTS
PHASE 1
EXCAVATION AND DEWATERING

DATE: FEBRUARY 2020
HAZEN NO.: 31419-000

FIGURE NO.


1.1



NOISE MONITORING NOTES:

1. CONTRACTOR SHALL MONITOR AND DOCUMENT BASELINE NOISE LEVELS AT THREE (3) OR MORE LOCATIONS NEAR THE IDENTIFIED RECEPTOR LOCATIONS DURING NON-WORKING PERIODS.
2. CONTRACTOR SHALL MONITOR AND DOCUMENT NOISE LEVELS AT THE SAME RECEPTOR LOCATIONS DURING THE PEAK ACTIVITY PERIOD.
3. CONTRACTOR SHALL USE A TYPE 2 / CLASS 2 SOUND LEVEL METER THAT MEETS OR EXCEEDS IEC 61672.

MATCH LINE - SEE THIS SHEET



NOISE GENERATION AND IMPACTS

PHASE	ACTIVITY	DAY	NIGHT	EQUIPMENT	QUANTITY	ACCUSTICAL USE FACTOR (%) *	WORK DESCRIPTION	RECEPTOR *	DISTANCE TO RECEPTOR (ft)	COMBINED CALCULATED (dBA) †		LIMITS (dBA) (Day) *		LIMITS (dBA) (Night) *		SHIELDING (Dba) †	COMBINED CALCULATED EXCEEDANCE (dBA) †		NOTES / ACTIONS
										Lmax	L10	Lmax	L10	Lmax	L10		Day	Night	
0	Construction Entrance	Yes	No	Dump Truck	5	40%	Delivery and removal of materials.	Residential homes	30	77.9	76.9	85	75	80	35	3	1.9	N/A	Exceedance is minimal. Receptor is the residential property that fronts Providence Road, therefore anticipated Daytime Baseline is likely to be at or exceeding the calculated noise level.
1	Excavation	Yes	No	Excavator	2	40%	Waterline installation along eastern property boundary.	Residential homes	300	77.9	78.6	85	75	80	35	3.0	3.6	N/A	No actions required
1	Excavation	Yes	No	Off-Road Dump Truck	3	40%	Waterline installation along eastern property boundary.	Residential homes	135										
1	Excavation	Yes	No	Dozer	1	40%	Maintenance of stockpile and site.	Residential homes	135										
1	Dewatering	Yes	Yes	Pumps (Per dba required)	2	100%	Dewatering of tank excavation.	Residential homes	500										
2	Pile Driving	Yes	No	Pile Driver Impact	1	20%	Pile Driving for tank foundation.	Residential homes	530	77.8	73.8	85	75	80	35	3	No Exceedance	N/A	No actions required
2	Pile Driving	Yes	No	Use Crane, Derrick	1	16%	Crane for pile driving	Residential homes	480										
2	Dewatering	Yes	Yes	Pumps (Per dba required)	2	100%	Dewatering of tank excavation.	Residential homes	500	57.9	57.9	85	75	80	35	3.0	No Exceedance	22.9	Exceedance is minimal. Consider application of an Acoustic Shadow/Barrier such as straw bails or other. Combine with receptor perimeter monitoring.
3	Utility Installation	Yes	No	Backhoe	1	40%	Waterline installation along eastern property boundary.	Residential homes	30	79.0	78.0	85	75	80	35	3.0	3.0	N/A	Exceedance is minimal. Possible additional shielding will occur via existing vegetation and stockpile storage area. Install receptor perimeter monitoring and potential remediation of proximity related equipment.
3	Utility Installation	Yes	No	Compactor	1	40%	Waterline installation along eastern property boundary.	Residential homes	30	84.7	80.7	85	75	80	35	3.0	5.7	N/A	
3	Utility Installation	Yes	No	Loader	1	40%	Waterline installation along eastern property boundary.	Residential homes	30	80.5	79.6	85	75	80	35	3.0	4.6	N/A	
3	Tank Construction	Yes	No	Use Crane, Derrick	2	16%	Tank construction consisting of concrete placement and precast element placement.	Residential homes	480	60.4	61.4	85	75	80	35	3.0	No Exceedance	N/A	
3	Tank Construction	Yes	No	Concrete Mixers	2	15%		Residential homes	480										
3	Tank Construction	Yes	No	Concrete Vibrator	1	15%	Cast in place concrete placement.	Residential homes	480										
3	Tank Construction	Yes	No	Air Compressor	1	15%	For use near tank...	Residential homes	480										
3	Tank Construction	Yes	No	Loader	1	40%	For use on site-wide soil and material placement.	Residential homes	480										
4	Backfill & Final Grading	Yes	No	Excavator	1	40%	Backfilling of excavated areas and site-wide grading.	Residential homes	135	69.1	71.7	85	75	80	35	3.0	No Exceedance	N/A	No actions required
4	Backfill & Final Grading	Yes	No	Off-Road Dump Truck	2	40%	Backfilling of excavated areas and site-wide grading.	Residential homes	135										
4	Backfill & Final Grading	Yes	No	Roller	1	40%	Backfilling of excavated areas and site-wide grading.	Residential homes	250										
4	Backfill & Final Grading	Yes	No	Grader	1	40%	Backfilling of excavated areas and site-wide grading.	Residential homes	250	76.2	76.1	85	75	80	35	3.0	1.1	N/A	Exceedance is minimal. No actions required.
4	Backfill & Final Grading	Yes	No	Paver	1	40%	Paving of Barco Drive	Residential homes	40										

* NOTE: All calculations and noise data were developed using the Roadway Construction Noise Model (RCNM) developed by the Federal Highway Administration (FHWA), Version 1.1, 12/08/2008



PROJECT ENGINEER:	T. McPHERSON
DESIGNED BY:	T. McPHERSON / C. LINK
DRAWN BY:	M. BRANDT
CHECKED BY:	T. McPHERSON
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO FULL SCALE	0 1/2" 1"
REV	ISSUED FOR
DATE	BY

Hazen
HAZEN AND SAWYER
4500 MAIN STREET, SUITE 500
VIRGINIA BEACH, VIRGINIA 23462
PHONE: 757-497-0490

CROWDER CONSTRUCTION COMPANY
11111 BURMA DRIVE
APEX, NORTH CAROLINA 27539
PHONE: 800-849-5449


VB
City of
Virginia Beach

HRSD
PROVIDENCE ROAD OFF-LINE
STORAGE FACILITY AND WOODSTOCK
PARK IMPROVEMENTS


PRECONSTRUCTION ASSESSMENT
AND DAMAGE MITIGATION PLAN
NOISE GENERATION AND IMPACTS
PHASE 2
PILE DRIVING

DATE: FEBRUARY 2020
HAZEN NO.: 31419-000
FIGURE NO.

1.2




- NOISE MONITORING NOTES:
1. CONTRACTOR SHALL MONITOR AND DOCUMENT BASELINE NOISE LEVELS AT THREE (3) OR MORE LOCATIONS NEAR THE IDENTIFIED RECEPTOR LOCATIONS DURING NON-WORKING PERIODS.
 2. CONTRACTOR SHALL MONITOR AND DOCUMENT NOISE LEVELS AT THE SAME RECEPTOR LOCATIONS DURING THE PEAK ACTIVITY PERIOD.
 3. CONTRACTOR SHALL USE A TYPE 2 / CLASS 2 SOUND LEVEL METER THAT MEETS OR EXCEEDS IEC 61672.



NOISE GENERATION AND IMPACTS																			
PHASE	ACTIVITY	DAY	NIGHT	EQUIPMENT	QUANTITY	ACOUSTICAL USE FACTOR (%)	WORK DESCRIPTION	RECEPTOR *	DISTANCE TO RECEPTOR (ft)	COMBINED CALCULATED (dBA) *		LIMITS (dBA) (Day) *		LIMITS (dBA) (Night) *		SHIELDING (dBA) *	COMBINED CALCULATED EXCEEDANCE (dBA) *		NOTES / ACTIONS
										Lmax	L10	Lmax	L10	Lmax	L10		Day	Night	
0	Construction Entrance	Yes	No	Dump Truck	5	40%	Delivery and removal of materials.	Residential homes	30	77.9	76.9	85	75	80	35	3	1.9	N/A	Exceedance is minimal. Receptor is the residential property that fronts Providence Road, therefore anticipated Daytime Baseline is likely to be at or exceeding the calculated noise level.
1	Excavation	Yes	No	Excavator	2	40%	Waterline installation along eastern property boundary	Residential homes	300	77.9	78.6	85	75	80	35	3.0	3.6	N/A	No actions required
1	Excavation	Yes	No	Off-Road Dump Truck	3	40%	Waterline installation along eastern property boundary	Residential homes	135										
1	Excavation	Yes	No	Dozer	1	40%	Maintenance of stockpile and site.	Residential homes	135										
1	Dewatering	Yes	Yes	Pumps (Per dBA required)	2	100%	Dewatering of tank excavation.	Residential homes	500										
2	Pile Driving	Yes	No	Pile Driver Impact	1	20%	Pile Driving for tank foundation	Residential homes	530	77.8	73.8	85	75	80	35	3	No Exceedance	N/A	No actions required
2	Pile Driving	Yes	No	Use Crane, Derrick	1	16%	Crane for pile driving	Residential homes	480	57.9	57.9	85	75	80	35	3.0	No Exceedance	22.9	Exceedance is minimal. Consider application of an Acoustic Shadow/Barrier such as straw bails or other. Combine with receptor perimeter monitoring.
2	Dewatering	Yes	Yes	Pumps (Per dBA required)	2	100%	Dewatering of tank excavation.	Residential homes	500										
3	Utility Installation	Yes	No	Backhoe	1	40%	Waterline installation along eastern property boundary	Residential homes	30	79.0	78.0	85	75	80	35	3.0	3.0	N/A	Exceedance is minimal. Possible additional shielding will occur via existing vegetation and stockpile storage area. Install receptor perimeter monitoring and potential remediation of proximity related equipment.
3	Utility Installation	Yes	No	Compactor	1	40%	Waterline installation along eastern property boundary	Residential homes	30	84.7	80.7	85	75	80	35	3.0	5.7	N/A	
3	Utility Installation	Yes	No	Loader	1	40%	Waterline installation along eastern property boundary	Residential homes	30	80.5	79.6	85	75	80	35	3.0	4.6	N/A	
3	Tank Construction	Yes	No	Use Crane, Derrick	2	16%	Tank construction consisting of concrete placement and precast element placement.	Residential homes	480	60.4	61.4	85	75	80	35	3.0	No Exceedance	N/A	
3	Tank Construction	Yes	No	Concrete Mixers	2	15%		Residential homes	480										
3	Tank Construction	Yes	No	Concrete Vibrator	1	15%	Cast in place concrete placement.	Residential homes	480										
3	Tank Construction	Yes	No	Air Compressor	1	15%	For use near tank.	Residential homes	480										
3	Tank Construction	Yes	No	Loader	1	40%	For use on site-wide soil and material placement.	Residential homes	480										
4	Backfill & Final Grading	Yes	No	Excavator	1	40%	Backfilling of excavated areas and site-wide grading.	Residential homes	135	69.1	71.7	85	75	80	35	3.0	No Exceedance	N/A	No actions required
4	Backfill & Final Grading	Yes	No	Off-Road Dump Truck	2	40%	Backfilling of excavated areas and site-wide grading.	Residential homes	135										
4	Backfill & Final Grading	Yes	No	Roller	1	40%	Backfilling of excavated areas and site-wide grading.	Residential homes	250										
4	Backfill & Final Grading	Yes	No	Grader	1	40%	Backfilling of excavated areas and site-wide grading.	Residential homes	250										
4	Backfill & Final Grading	Yes	No	Paver	1	40%	Paving of Barco Drive	Residential homes	40	76.2	76.1	85	75	80	35	3.0	1.1	N/A	Exceedance is minimal. No actions required.

* NOTE: All calculations and noise data were developed using the Roadway Construction Noise Model (RCNM) developed by the Federal Highway Administration (FHWA). Version 1.1, 12/08/2008



PROJECT ENGINEER:	T. McPHERSON
DESIGNED BY:	T. McPHERSON / C. LINK
DRAWN BY:	M. BRANDT
CHECKED BY:	T. McPHERSON
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO FULL SCALE	0 1/2" 1"
REV	ISSUED FOR
DATE	BY

Hazen
HAZEN AND SAWYER
4500 MAIN STREET, SUITE 500
VIRGINIA BEACH, VIRGINIA 23462
PHONE: 757-497-0490


CROWDER CONSTRUCTION COMPANY
1111 BURMA DRIVE
APEX, NORTH CAROLINA 27539
PHONE: 800-849-5449

VB
City of
Virginia Beach


HRSD
PROVIDENCE ROAD OFF-LINE
STORAGE FACILITY AND WOODSTOCK
PARK IMPROVEMENTS

PRECONSTRUCTION ASSESSMENT
AND DAMAGE MITIGATION PLAN
NOISE GENERATION AND IMPACTS
PHASE 3
UTILITY AND TANK CONSTRUCTION

DATE: FEBRUARY 2020
HAZEN NO.: 31419-000
FIGURE NO.
1.3



- NOISE MONITORING NOTES:**
1. CONTRACTOR SHALL MONITOR AND DOCUMENT BASELINE NOISE LEVELS AT THREE (3) OR MORE LOCATIONS NEAR THE IDENTIFIED RECEPTOR LOCATIONS DURING NON-WORKING PERIODS.
 2. CONTRACTOR SHALL MONITOR AND DOCUMENT NOISE LEVELS AT THE SAME RECEPTOR LOCATIONS DURING THE PEAK ACTIVITY PERIOD.
 3. CONTRACTOR SHALL USE A TYPE 2 / CLASS 2 SOUND LEVEL METER THAT MEETS OR EXCEEDS IEC 61672.



NOISE GENERATION AND IMPACTS														
PHASE	ACTIVITY	DAY	NIGHT	EQUIPMENT	QUANTITY	ACOUSTICAL USE FACTOR (%) *	WORK DESCRIPTION	RECEPTOR *	DISTANCE TO RECEPTOR (ft)	COMBINED CALCULATED (dBA) *		LIMITS (dBA) (Day) *		NOTES / ACTIONS
										Lmax	L10	Lmax	L10	
0	Construction Entrance	Yes	No	Dump Truck	5	40%	Delivery and removal of materials.	Residential homes	30	77.9	76.9	85	75	Exceedance is minimal. Receptor is the residential property that fronts Providence Road, therefore anticipated Daytime Baseline is likely to be at or exceeding the calculated noise level.
1	Excavation	Yes	No	Excavator	2	40%	Waterline installation along eastern property boundary.	Residential homes	300					
1	Excavation	Yes	No	Off-Road Dump Truck	3	40%	Waterline installation along eastern property boundary.	Residential homes	135	77.9	78.6	85	75	No actions required
1	Excavation	Yes	No	Dozer	1	40%	Maintenance of stockpile and site.	Residential homes	135					
1	Dewatering	Yes	Yes	Pumps (Per dba required)	2	100%	Dewatering of tank excavation.	Residential homes	500					
2	Pile Driving	Yes	No	Pile Driver Impact	1	20%	Pile Driving for tank foundation	Residential homes	530	77.8	73.8	85	75	No Exceedance
2	Pile Driving	Yes	No	Use Crane, Derrick	1	15%	Crane for pile driving	Residential homes	480					N/A
2	Dewatering	Yes	Yes	Pumps (Per dba required)	2	100%	Dewatering of tank excavation.	Residential homes	500	57.9	57.9	85	75	22.9 Exceedance is minimal. Consider application of an Acoustic Shadow/Barrier such as straw bails or other. Combine with receptor perimeter monitoring.
3	Utility Installation	Yes	No	Backhoe	1	40%	Waterline installation along eastern property boundary.	Residential homes	30	79.0	78.0	85	75	
3	Utility Installation	Yes	No	Compactor	1	40%	Waterline installation along eastern property boundary.	Residential homes	30	84.7	80.7	85	75	
3	Utility Installation	Yes	No	Loader	1	40%	Waterline installation along eastern property boundary.	Residential homes	30	80.5	79.6	85	75	
3	Tank Construction	Yes	No	Use Crane, Derrick	2	15%	Tank construction consisting of concrete placement and precast element placement.	Residential homes	480					
3	Tank Construction	Yes	No	Concrete Mixers	2	15%		Residential homes	480	60.4	61.4	85	75	
3	Tank Construction	Yes	No	Concrete Vibrator	1	15%	Cast in place concrete placement.	Residential homes	480					
3	Tank Construction	Yes	No	Air Compressor	1	15%	For use near tank.	Residential homes	480					
3	Tank Construction	Yes	No	Loader	1	40%	For use on site-wide soil and material placement.	Residential homes	480					
4	Backfill & Final Grading	Yes	No	Excavator	1	40%	Backfilling of excavated areas and site-wide grading.	Residential homes	135					
4	Backfill & Final Grading	Yes	No	Off-Road Dump Truck	2	40%	Backfilling of excavated areas and site-wide grading.	Residential homes	135	69.1	71.7	85	75	
4	Backfill & Final Grading	Yes	No	Roller	1	40%	Backfilling of excavated areas and site-wide grading.	Residential homes	250					
4	Backfill & Final Grading	Yes	No	Grader	1	40%	Backfilling of excavated areas and site-wide grading.	Residential homes	250					
4	Backfill & Final Grading	Yes	No	Paver	1	40%	Paving of Barco Drive	Residential homes	40	76.2	76.1	85	75	

* NOTE: All calculations and noise data were developed using the Roadway Construction Noise Model (RCNM) developed by the Federal Highway Administration (FHWA). Version 1.1, 12/08/2008



				PROJECT ENGINEER:	T. McPHERSON
				DESIGNED BY:	T. McPHERSON / C. LINK
				DRAWN BY:	M. BRANDT
				CHECKED BY:	T. McPHERSON
				IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO FULL SCALE	0 1/2" 1"
REV	ISSUED FOR	DATE	BY		

Hazen
HAZEN AND SAWYER
4500 MAIN STREET, SUITE 500
VIRGINIA BEACH, VIRGINIA 23462
PHONE: 757-497-0490

CROWDER CONSTRUCTION COMPANY
11111 BURMA DRIVE
APEX, NORTH CAROLINA 27539
PHONE: 800-849-5449

VB
City of
Virginia Beach


HRSD
PROVIDENCE ROAD OFF-LINE
STORAGE FACILITY AND WOODSTOCK
PARK IMPROVEMENTS

PRECONSTRUCTION ASSESSMENT
AND DAMAGE MITIGATION PLAN
NOISE GENERATION AND IMPACTS
PHASE 4
BACKFILL & FINAL GRADING

DATE: FEBRUARY 2020
HAZEN NO.: 31419-000
FIGURE NO.
1.4



VIBRATION MONITORING NOTES:
CONTRACTOR SHALL PREPARE A VIBRATION MONITORING PLAN PER SPECIFICATION SECTION 02367. THE PLAN SHALL INCLUDE:
- PHOTO DOCUMENT THE CONDITION OF ALL SITE STRUCTURES WITHIN THE PROJECTED 200 FT. ZONE OF INFLUENCE THAT WILL REMAIN DURING CONSTRUCTION IN PARTICULAR DOCUMENTATION OF THE EXISTING DOMINION ENERGY STRUCTURES.
- MONITOR AND DOCUMENT BASELINE VIBRATION LEVELS AT THREE (3) OR MORE LOCATIONS NEAR THE IDENTIFIED RECEPTOR BOUNDARY DURING NON-WORKING PERIODS.
- MONITOR AND DOCUMENT VIBRATION LEVELS AT THE SAME RECEPTOR LOCATIONS DURING THE PEAK ACTIVITY PERIOD.

MATCH LINE - SEE THIS SHEET



VIBRATION GENERATION AND IMPACTS						
PHASE	ACTIVITY	EQUIPMENT	PPV(25ft) (In/Sec)	Distance to Receptor (ft)	PPV(equip) (In/Sec)	NOTES / ACTIONS
0	Construction Entrance	Dump Truck	0.076	30	0.0578	Noticable but very safe to buildings
1	Excavation	Excavator	0.089	300	0.0021	Barely perceptible
1	Excavation	Off-Road Dump Truck	0.076	135	0.0061	Barely perceptible
1	Excavation	Dozer	0.089	135	0.0071	Barely perceptible
1	Dewatering	Pumps (Per dba required)	0	500	0.0000	Imperceptible
2	Pile Driving	Pile Driver Impact	1.518	480	0.0180	Strongly Noticable but very safe to buildings
2	Pile Driving	Use Crane, Derrick	0.003	481	0.00004	Imperceptible
2	Dewatering	Pumps (Per dba required)	0	482	0.0000	Imperceptible
3	Utility Installation	Backhoe	0.089	30	0.0677	Easily noticable but very safe to buildings
3	Utility Installation	Compactor	0.089	30	0.0677	Easily noticable but very safe to buildings
3	Utility Installation	Loader	0.089	30	0.0677	Easily noticable but very safe to buildings
3	Tank Construction	Use Crane, Derrick	0.003	480	0.0000	Imperceptible
3	Tank Construction	Concrete Mixers	0	480	0.0000	Imperceptible
3	Tank Construction	Concrete Vibrator	0	480	0.0000	Imperceptible
3	Tank Construction	Air Compressor	0	480	0.0000	Imperceptible
3	Tank Construction	Loader	0.003	480	0.0000	Barely perceptible
4	Backfill & Final Grading	Excavator	0.089	135	0.0071	Barely perceptible
4	Backfill & Final Grading	Off-Road Dump Truck	0.076	135	0.0061	Barely perceptible
4	Backfill & Final Grading	Roller	0.21	250	0.0066	Barely perceptible
4	Backfill & Final Grading	Grader	0.003	250	0.0001	Imperceptible
4	Backfill & Final Grading	Paver	0.003	40	0.0015	Imperceptible

SCALE: 1" = 60'



PROJECT ENGINEER:	T. McPHERSON
DESIGNED BY:	T. McPHERSON / C. LINK
DRAWN BY:	M. BRANDT
CHECKED BY:	T. McPHERSON
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO FULL SCALE	0 1/2" 1"
REV	ISSUED FOR
DATE	BY

Hazen
HAZEN AND SAWYER
4500 MAIN STREET, SUITE 500
VIRGINIA BEACH, VIRGINIA 23462
PHONE: 757-497-0490

CROWDER CONSTRUCTION COMPANY
1111 BURMA DRIVE
APEX, NORTH CAROLINA 27539
PHONE: 800-849-5449

VB
City of
Virginia Beach

HRSD
PROVIDENCE ROAD OFF-LINE
STORAGE FACILITY AND WOODSTOCK
PARK IMPROVEMENTS

PRECONSTRUCTION ASSESSMENT
AND DAMAGE MITIGATION PLAN
VIBRATION IMPACTS

DATE: FEBRUARY 2020
HAZEN NO.: 31419-000
FIGURE NO. 2