



NOTES:

- 1. PUMP CABLE WIRES SHALL BE SPLICED IN THE POWER WIRING JUNCTION BOX USING INSULATED MECHANICAL LUGS.
- 2. PROVIDE A MINIMUM OF 2' OF CABLE SLACK IN THE JUNCTION BOX.
- 3. THE INSTRUMENT VAULT AND VALVE VAULT ARE CLASSIFIED AS A CLASS 1, DIVISION 2, GROUP D AREA IN ACCORDANCE WITH NFPA 820. THE INSTALLATION OF ALL ELECTRICAL EQUIPMENT AND CONDUIT SHALL BE PERFORMED IN ACCORDANCE WITH THIS CLASSIFICATION.
- 4. ALL CONDUIT PENETRATIONS THROUGH CONCRETE STRUCTURES SHALL BE INSTALLED THROUGH SLEEVED PENETRATIONS WITH MODULAR SEALS AND 316 STAINLESS STEEL HARDWARE.







NOTES:

- 1. ANY DEVIATIONS FROM THIS DETAIL SHALL BE COORDINATED WITH HRSD OR HRSD'S REPRESENTATIVE.
- 2. ALL FASTENERS AND MOUNTING HARDWARE USED FOR INSTALLATION OF ELECTRICAL ITEMS SHALL BE OF THE SAME MATERIAL, GALVANIZED STEEL OR STAINLESS STEEL.
- 3. GALVANIZED STEEL ANTENNA MASTS SHALL NOT COME IN DIRECT CONNECT WITH THE GROUND. PROVIDE A BLOCK FOR ISOLATION IF REQUIRED.
- 4. DIRECTIONAL ANTENNA SHALL BE INSTALLED AT THE PROPER HEIGHT AND AZIMUTH ACCORDING TO THE SITE SURVEY.
- 5. DIRECTIONAL ANTENNA SHALL BE MOBILE MARK #PND10-700/2700.
- 6. COAX CABLE CONNECTORS SHALL BE INSTALLED PER MANUFACTURER REQUIREMENTS. SOLDERED CONNECTIONS ARE PREFERRED, CRIMP AND CAPTIVATED CONNECTIONS WILL BE ACCEPTED WHEN NECESSARY.
- 7. COAX CABLE CONNECTORS SHALL BE WEATHERPROOFED USING HEAT SHRINK OR COLD SHRINK TUBING, ELECTRICAL TAPE IS NOT ACCEPTABLE.
- 8. SUPPORT CONDUIT, COAX CABLE, AND GROUND CONDUCTORS AS REQUIRED PER THE NEC.
- 9. THROUGH WALL PENETRATION SHALL INCLUDE A SUITABLE SLEEVE. SEAL BETWEEN WALL AND SLEEVE. SEAL INTERIOR OF SLEEVE AFTER INSTALLATION OF THE COAX CABLES.
- 10. RUN A #6 GROUND CONDUCTOR FROM THE GROUND BUS TO THE BUILDING GROUNDING ELECTRODE SYSTEM. CONNECTION TO A SUPPLEMENTAL GROUND IS NOT ACCEPTABLE.
- 11. LIGHTNING ARRESTORS SHALL BE POLYPHASER #TSX-DFF OR #TSX-NFF MOUNTED ON THE OUTSIDE OF THE PUMP STATION NEAREST TO THE COAX CABLE POINT OF ENTRY USING AN APPROVED MOUNTING BRACKET.
- 12. GROUND CONDUCTORS FROM THE LIGHTNING ARRESTOR TO THE GROUND BUS SHALL NOT EXCEED 36 INCHES.
- 13. LIGHTNING ARRESTORS TO BE MOUNTED ON OUTSIDE OF BUILDING.
- 14. LMR-240 CABLE SHALL NOT EXCEED 75 LINEAR FEET.
- 15. COAX CABLE CONNECTORS AT THE ROUTER / RADIO SHALL BE TNC MALE CONNECTORS.

(C) HRSD	STANDARD DESIGN DETAIL	701B
	ANTENNA INSTALLATION	2 OF 2 DATE 7/2025







INTRINSIC SAFETY PANEL PANEL LAYOUT

NOTES:

- 1. INTRINSIC SAFETY PANEL SHALL BE MOUNTED ON OUTSIDE OF BUILDING OR EQUIPMENT RACK.
- 2. CONDUITS FROM TRANSDUCER AND FLOAT SWITCH CABLES ENTERING INTRINSIC SAFETY PANEL REQUIRE NO SEAL OFF FITTINGS.
- 3. INCLUDE SOURCE DESIGNATION (E.X. LSH-XXX) AS IT APPEARS IN THE P&ID IN ALL INPUT LABELS.









NOTES:

- THE INSTRUMENT VAULT AND VALVE VAULT ARE CLASSIFIED AS A CLASS 1, DIVISION 2, GROUP D AREA IN ACCORDANCE WITH NFPA 820. THE INSTALLATION OF ALL ELECTRICAL EQUIPMENT AND CONDUIT SHALL BE PERFORMED IN ACCORDANCE WITH THIS CLASSIFICATION.
- 2. ALL CONDUIT PENETRATIONS THROUGH CONCRETE STRUCTURES SHALL BE INSTALLED THROUGH SLEEVED PENETRATIONS WITH MODULAR SEALS AND 316 STAINLESS STEEL HARDWARE.
- 3. PROVIDE A BARRIER BETWEEN POWER AND CONTROL WIRING.







WIRING LEGEND:

- 1 DISCHARGE FLOW METER TRANSDUCER CABLES-1"C TO DISCHARGE FLOW METER TRANSMITTER
- (2) 2#14-3/4"C TO INTRINSIC SAFETY PANEL
- (3) 1 PR. #18 SHLD. TO INTRINSIC SAFETY PANEL. RUN IN 3/4"C TO JUNCTION BOX IN INSTRUMENT VAULT AND IN 3/4" TO INTRINSIC SAFETY PANEL

NOTES:

- 1. THE INSTRUMENT VAULT AND VALVE VAULT ARE CLASSIFIED AS A CLASS 1, DIVISION 2, GROUP D AREA IN ACCORDANCE WITH NFPA 820. THE INSTALLATION OF ALL ELECTRICAL EQUIPMENT AND CONDUIT SHALL BE PERFORMED IN ACCORDANCE WITH THIS CLASSIFICATION.
- 2. ALL CONDUIT PENETRATIONS THROUGH CONCRETE STRUCTURES SHALL BE INSTALLED THROUGH SLEEVED PENETRATIONS WITH MODULAR SEALS AND 316 STAINLESS STEEL HARDWARE.
- 3. PROVIDE A BARRIER BETWEEN POWER AND CONTROL WIRING.
- 4. ENSURE THAT THE MINIMUM STRAIGHT-PIPE DISTANCE BEFORE AND AFTER THE FLOW METER AS SPECIFIED BY THE EQUIPMENT MANUFACTURER IS MET.
- 5. MAGNETIC FLOW METERS MUST BE DIRECT BURIAL TYPE AND INSTALLED TO THE MANUFACTURERS REQUIRED MINIMUM UPSTREAM AND DOWNSTREAM STRAIGHT PIPE DISTANCES. AS THESE WILL BE INSTALLED IN VAULTS, THEY WILL REQUIRE THE ABILITY TO BE SUBMERGED.
- 6. DISCHARGE PRESSURE TRANSMITTERS MUST BE INSTALLED TO THE MANUFACTURERS REQUIREMENTS. AS THESE WILL BE INSTALLED IN VAULTS, THEY WILL REQUIRE THE ABILITY TO BE SUBMERGED.







WIRING LEGEND:


- 1 ACTUATOR POWER WIRING-3/4"C TO ACTUATOR VAULT JUNCTION BOX
- 2 ACTUATOR CONTROL WIRING-1"C TO ACTUATOR VAULT JUNCTION BOX
- (3) 2#14-3/4"C TO INTRINSIC SAFETY PANEL

NOTES:


- THE INSTRUMENT VAULT AND VALVE VAULT ARE CLASSIFIED AS A CLASS 1, DIVISION 2, GROUP D AREA IN ACCORDANCE WITH NFPA 820. THE INSTALLATION OF ALL ELECTRICAL EQUIPMENT AND CONDUIT SHALL BE PERFORMED IN ACCORDANCE WITH THIS CLASSIFICATION.
- 2. ALL CONDUIT PENETRATIONS THROUGH CONCRETE STRUCTURES SHALL BE INSTALLED THROUGH SLEEVED PENETRATIONS WITH MODULAR SEALS AND 316 STAINLESS STEEL HARDWARE.
- 3. PROVIDE A BARRIER BETWEEN POWER AND CONTROL WIRING.































NOTE: ALL CONTACTS ARE SHOWN IN THE DE-ENERGIZED STATE

(C) HRSD	STANDARD DESIGN DETAIL	713 SHEET
	SCHEMATIC FOR PUMP RUN STATUS WIRING TO LOCAL PLC	1 OF 1 DATE 7/2025





FREE STANDING EQUIPMENT MOUNTING RACK FOR MOTORS LESS THAN 100 HP NOTES:

- 1. ANCHOR POST BASES TO CONCRETE WITH MINIMUM 4 3/8" DIA STAINLESS STEEL EXPANSION ANCHOR BOLTS (HILTI "KWIK II", OR EQUAL) PER BASE AT MINIMUM 2" EMBEDMENT.
- 2. PROVIDE MELTRIC PLUG AND RECEPTACLE, SIZED FOR MOTOR HORSE POWER, SWITCH RATED DISCONNECTING MEANS, WITH 6 AUXILIARY CONTACTS. PROVIDE CABLE STRAIN RELIEF.
- 3. JUNCTION BOX FOR MOUNTING OF MELTRIC PLUG AND RECEPTACLE SHALL BE SIZED PER NEC FOR BENDING RADIUS OF THE CONDUCTORS.

FREE STANDING EQUIPMENT MOUNTING RACK FOR 150HP MOTORS NOTES:

- 1. ANCHOR POST BASES TO CONCRETE WITH MINIMUM 4 3/8" DIA STAINLESS STEEL EXPANSION ANCHOR BOLTS (HILTI "KWIK II", OR EQUAL) PER BASE AT MINIMUM 2" EMBEDMENT.
- 2. PROVIDE MELTRIC PLUG AND RECEPTACLE RATED FOR AMPERAGE OF MOTOR WITH 6 AUXILIARY CONTACTS. PROVIDE CABLE STRAIN RELIEF.
- 3. JUNCTION BOX FOR MOUNTING MELTRIC PLUG AND RECEPTACLE SHALL BE SIZED PER NEC FOR BENDING RADIUS OF THE CONDUCTORS.

NOT TO SCALE



STANDARD DESIGN DETAIL


DRAWING NO.
714C
SHEET

3 OF 4

FREE STANDING EQUIPMENT MOUNTING RACK

DATE 7/2025


INSTRUMENTATION CABLE JUNCTION BOX




NOTES:

- 1. PROVIDE COMPRESSION LUGS FOR ALL WIRING. TERMINAL BLOCKS TO BE STUD TYPE FOR USE WITH COMPRESSION LUGS.
- 2. SIZE JUNCTION BOX TO PROVIDE SPACE FOR PUMP MONITORING DEVICE PROVIDED BY PUMP MANUFACTURER.
- 3. WIRE BENDING SPACE AT TERMINALS SHALL BE PER NEC ARTICLE 312.
- 4. PROVIDE CONDUIT SEAL-OFF FITTINGS WHERE REQUIRED.







TO DETERMINE DEFLECTION (INCHES) AT ANY LESSER LOAD, MULTIPLY THE ACTUAL LOAD (LBS/FT) BY THE DEFLECTION MULTIPLIER

NOTE:

VALUES ARE BASED ON SIMPLE BEAM TESTS PER NEMA VE-1 ON 36" WIDE CABLE TRAY WITH RUNGS SPACED ON 12" CENTERS. THE PUBLISHED LOAD SAFETY FACTOR IS 1.5. TO CONVERT 1.5 SAFETY FACTOR TO 2.0, MULTIPLY THE PUBLISHED LOAD BY 0.75. TO OBTAIN MID-SPAN DEFLECTION, MULTIPLY THE LOAD BY THE DEFECTION MULTIPLIER. CABLE TRAY MUST BE SUPPORTED ON SPANS SHORTER THAN OR EQUAL TO THE LENGTH OF THE TRAY.

