

HRSD Design and Construction Standards - January 2019

Table of Contents

Section No.	Subject	Page No.
Forward	Engineering Director's Viewpoint	Forward
1.	Introduction	1-1
	A. Purpose	
	B. Expectations, Outcomes and Sustainability	
	C. Project Delivery Methods	
	D. Distribution	
	E. Preparation of Design Documents	
	1. General Requirements	
	2. Study and Preliminary Engineering Report (PER)	
	3. Project Manual (Contract Requirements, Technical Specifications and Construction Drawings)	
	F. Common Historical Issues in the Design and Construction Phase	
	1. Design Phase	
	2. Construction Phase	
	G. Use of Autonomus Vehicles (AV)	
2.	Architectural and Landscaping Design and Review Process	2-1
	A. Introduction	
	B. HRSD Architectural Review Committee (ARC)	
	C. Attachments	
	Attachment A - Pump Station Architectural Guidelines.	A
	Attachment B - Aesthetics Consideration Log	B
	Attachment C - Address Sign Specification	C
	Attachment D - Safety Sign Specification for Buildings	D
	Attachment E - Landscaping Planting Plan sample	E
3.	Use of Technical Memorandum for CIP Projects	3-1
	A. Introduction	
	B. Circumstances for Use	
	C. Approval for Use	
4.	Monthly Project Status Reporting	4-1
	A. Introduction	
	B. Content and Format for Project Status Report (Part 1)	
	C. Content and Format for Project Expenditure Tracking (Part 2)	
	Exhibit A – FIRM Progress Report Template	
	Exhibit B – Project Expenditure Tracking Template	
5.	Capital Project Cost, Schedule and Risk Reporting	5-1
	A. Introduction	
	B. Professional Services Firm (FIRM) Responsibilities	

Section No.	Subject	Page No.
	C. Exhibit A - Example Report	
6.	Drawings, Record Drawings, and Valve Guides	6-1
	A. Introduction	
	B. Drawings	
	C. Record Drawings	
	D. Bid Documents	
	E. Valve Guides	
	Exhibit A: Valve Guide Format and Examples	
7.	PER, Design, and Construction Submittal Requirements	7-1
	A. Introduction	
	B. Requirement for Submittals	
	1. Format for Digital Files	
	2. Seamless AutoCAD Files	
	3. Interim Record Drawings	
	4. Interim Valve Guides	
	5. Final Record Drawings	
	6. Final Valve Guides	
	7. Shop Drawings	
	8. Operation and Maintenance (O&M) Manuals	
	9. Conformed Documents	
	10. Building Information Model (BIM) Execution Plans	
	Attachment A – Summary of Major Submittals to HRSD	A
	Attachment B – Equipment Record Template (Excel)	B
8.	Real Estate Acquisition and Plat Guidelines	8-1
	A. Introduction	
	B. Real Estate Schedule vs. Project Schedule	
	C. Easements	
	Exhibit A – Real Estate Schedule vs. Project Schedule	
9.	Flood Elevation Requirements	9-1
	A. Introduction	
	B. Definitions	
	C. Locality Code Requirement	
	D. Steps for Determining Construction Elevation	
	E. Elevation Requirement Example	
10.	Public Participation Program	10-1
	A. Introduction	
	B. Public Participation Program	
	1. Engage with Locality Staff	

Section No.	Subject	Page No.
	2. Identify Project Stakeholders	
	3. Participate in Public Open House / Community Meetings	
	4. Alert Public Officials	
	5. Distribute Project Introductory Notice to Neighbors	
	6. Post Project Signs	
	7. Post Variable Message Boards (VMB)	
	8. Establish Project Website	
	9. Issue Media Releases	
	10. Response to Public and Media Inquires	
	11. Provide Project Updates	
	12. Coordination with Locality Public Information Staff	
	Attachment A - Public Participation Program – Project Manager Checklist	A
	Attachment B - Stakeholders List Template	B
	Attachment C - Sample – Willingness to Hold	C
	Attachment D - Sample - Public Meeting Advertisement	D
	Attachment E - Open House Notice to Public Template	E
	Attachment F - Public Meeting Requirements	F
	Attachment G - Sample - Project Sign-In Sheet	G
	Attachment H - Sample - Project Comment Sheet	H
	Attachment I - Advertisement Submission Schedule	I
	Attachment J - Project Introductory Notice to Neighbors – Template	J
	Attachment K - Sample – CIP Project Sign	K
	Attachment L - Sample - HRSD Sign Specifications	L
	Attachment M - HRSD Sign and Base Specifications	M
	Attachment N - New Project Webpage – Template	N
	Attachment O - New Project FAQs – Template	O
	Attachment P - New Project Map - Template	P
	Attachment Q - Wet Weather/Locality Program Neighborhood Map - Template	Q
	Attachment R - Sample – Media Release – Traffic Advisory	R
	Attachment S - Sample – Media Release – Incident Statement	S
	Attachment T - Sample – Media Cards (Media/Project Inquiries)	T
	Attachment U - Sample - Website Update (Unifier)	U
	Attachment V - Construction Update Notices – Template	V
	Attachment W - CCTV Inspection Notice to Neighbors - Template	W
	Attachment X - CCTV Cleaning and Inspection Notice to Neighbors - Template	X
	Attachment Y - Smoke Testing Notice and Door Knob Hanger - Template	Y

Section No.	Subject	Page No.
	Attachment Z - Survey Notice to Neighbors - Template	Z
	Attachment AA - Reminder Notice to Neighbors (one week/48 hours) - Template	AA
	Attachment BB - Reminder Notice to Neighbors (day of work) - Template	BB
	Attachment CC - Completed Work Notice to Neighbors - Template	CC
	Attachment DD - Project Closeout Notice - Template	DD
	Attachment EE - Survey Notices – Mailing and Tracking Log – Template	EE
	Attachment FF - Stakeholder Email Update - Template	FF
11.	Preconstruction Assessments and Damage Mitigation Procedures	11-1
	A. Introduction	
	B. Organization of Section	
	1. Stage 1 – Construction Impact Research and Evaluation	
	a. Research and Investigations during Design Phase	
	b. Determinations during the Design Phase	
	c. Potential of Construction Related Impacts	
	i. Noise Generation and Impacts	
	ii. Vibration Impacts	
	iii. Dewatering Impacts on Ground and Structure Settlement	
	iv. Construction Impacts on Existing Topography, Hard Surfaces, Hydrology, and Construction Travel Routes	
	v. Dust, Odor, and Other Emissions Beyond Construction Zone	
	d. Determination of construction zone of influence for all potential construction related impacts	
	2. Stage 2 – Risk Mitigation Analysis and Bid Document Development for Contractor Actions	
	a. Noise Impacts, Restrictions, and Abatement	
	b. Vibration Impacts, Abatement, and Monitoring	
	c. Groundwater Dewatering Requirements	
	d. Pre-Construction Surveys and Assessments within Construction Corridors and Impact Areas	
	e. Fugitive Emissions Controls and Restrictions	
	3. Stage 3 – Specific Pre-Construction Field Surveys and Construction Activity Monitoring Programs	
	a. Responsibilities of the FIRM	
	b. Responsibilities of the Contractor	
	c. Identification of Other Party Responsibilities	

Section No.	Subject	Page No.
	Attachment A - Pre-Construction Conditions Assessment Communications and Contact Tracking Log Template	A
	Attachment B - Right to Access Property Form Template	B
	Attachment C - Assessment of Pre-Existing Conditions Request Letter Template	C
	Attachment D - Pre-Existing Condition Assessment Reporting Form Template	D
12.	Coordination with Virginia DEQ for Certificate to Construction, Certificate to Operate and Tax Exemptions for Qualifying Sanitary Sewer Projects	12-1
	A. Introduction	
	B. Approval CTC Process for State Water Quality Improvement Fund (WQIF) Projects	
	C. Abbreviated Administrative Process for Non-WQIF Projects	
	D. Approval Process for Non-WQIF Projects that Involve Greater than 25% Capacity Increase or Decrease	
	E. Relocation, Replacement-In-Kind, Maintenance or Emergency Projects	
	F. Online Resources within DEQ for Approval Process	
	Exhibits A thru D – Template Letters to DEQ	
13.	Coordination of Preconstruction Phase Issues	13-1
	A. Introduction	
	B. Coordination with Engineering Contract Specialist	
14.	Preparation of and Format for Construction Addenda	14-1
	A. Introduction	
	B. Guidelines and Specific Requirements	
	C. Exhibit A - Addendum Template	
15.	Preparation of and Format for Conformed Documents	15-1
	A. Introduction	
	B. Specifications	
	C. Drawings	
	D. Format and Number of Conformed Documents	
16.	Tracking of Construction Phase Milestones and Performance Metrics	16-1
	A. Introduction	
	B. Completion and Submittal of Construction Milestone Tracking Form	
	C. Performance Metrics	
	Exhibit A - Active Construction Project Tracking Form	Exhibit A

Section No.	Subject	Page No.
17.	Expectations for Construction Administration and Construction Inspection	17-1
	A. Introduction	
	B. Organization of Section	
	C. General Expectations	
	D. Preconstruction	
	E. General Procedures	
	F. Tie-In, Shutdown, and Diversion Procedures	
	G. Line Stop Procedures	
	H. Trenchless Crossing Procedures	
	I. Damage Assessment and Claims Procedures	
	J. Training	
	K. Record Keeping	
	L. Staffing	
	M. Verification	
18.	Use of Air Vent Proving Tool	18-1
	A. Introduction	
	B. FIRM Responsibilities and Procedures	
19.	Condition Assessment Protocol for Replaced or Abandoned Pipelines	19-1
	A. Introduction	
	B. Condition Assessment During PER Phase	
	C. Technical Specification	
	D. Checklist	
20.	Regulatory Reporting Requirements for Spills	20-1
	A. Introduction	
	B. Procedures	
	C. Contact Information	
21.	HRSD Safety Programs	21-1
	A. Introduction	
	B. Safety Programs	
	1. Hazard Communication Program	
	2. Hot Work Permit Program	
	3. Lock Out / Tag Out Program	
	4. Confined Space Entry Program	
	5. Plant Access Procedures for Contractors	
	6. NFPA 70E	
	7. Fall Protection	
	8. Correction of Safety Issues	

Section No.	Subject	Page No.
	9. Excavations and Trenching	
	10. Fire Protection Systems	
	11. Housekeeping	
	12. Outside Contractor Briefing	
	13. Asbestos Awareness Program	
	14. Weapons Policy	
	15. Use of HRSD Equipment	
	Exhibit A - Asbestos Checklist	Exhibit A
22.	VDOT 2011 Work Area Protection Manual (WAPM) Requirements	22-1
	A. Introduction	
	B. Training Requirements for Construction Inspectors	
	C. Personal Protective Equipment (PPE) Requirements	
23.	Pipelines and Appurtenances	23-1
	A. Introduction	
	B. General	
	1. Design Specifics	
	2. Corrosion Prevention	
	3. Protective Linings	
	4. Bid Document Development	
	C. Force Mains	
	1. Design Specifics	
	2. Hydrostatic Pressure Test Procedures	
	D. Line Stops	
	1. Guidelines for Use	
	2. Design Considerations	
	3. Qualifications to be Incorporated Into Bid Documents	
	4. Liquidated Damages	
	E. Valves	
	1. Gate Valves and Plug Valves	
	2. Disposition of Existing Inline Valves to be Abandoned	
	3. Automatic Air Release Valves	
	F. Gravity Interceptors and Manholes	
	Exhibit A – Report of Hydrostatic Pressure Test	
24.	Checklist for Line Stop Installations	24-1
	A. Introduction	
	B. Completion and Submittal of Checklist for Line Stop Installations	
	Exhibit A – Checklist for Line Stop Installation Form	Exhibit A
25.	Checklist for Tie-Ins to Existing Interceptor Force Mains	25-1
	A. Introduction	

Section No.	Subject	Page No.
	B. Completion and Submittal of Checklist for Tie-Ins to Existing Interceptor Force Mains	
	Exhibit A - HRSD Checklist for Tie-Ins to Existing Interceptor Force Mains	Exhibit A
26.	Trenchless Installations and Rehabilitation	26-1
	A. Introduction	
	B. General Evaluation Criteria	
	C. New Trenchless Pipe Installations	
	1. Horizontal Directional Drilling (HDD)	
	2. Jack & Bore and Microtunneling	
	3. Ground Penetrating Radar (GPR) Use	
	D. Sanitary Sewer System Rehabilitation	
	1. Cleaning	
	2. Closed-Circuit Television Video (CCTV)	
	3. Diversion Pumping	
	4. Gravity Sewer Rehabilitation	
	a. Cured In Place Pipe (CIPP)	
	b. Folded and Reformed Liners	
	c. Formed In Place Pipe (FIPP)	
	d. Sliplining	
	e. Pipe Bursting	
	5. Lateral Reinstatement	
	6. Manhole Rehabilitation	
	7. Wet Well Rehabilitation	
	8. Post Construction & Rehabilitation Evaluation for Gravity Sewer Mains and Manholes	
	Exhibit A - Manhole Protective Coating Post Installation Certification Form	Exhibit A
27.	Checklist for Trenchless Crossing Operations	27-1
	A. Introduction	
	B. Completion and Submittal of Checklist for Trenchless Crossing Operations	
	Exhibit A – HRSD Checklist for Trenchless Crossing Operations	Exhibit A
28.	Pump Stations	28-1
	A. Introduction	
	B. Description of Operations	
	1. Wet Well Pump Station	
	2. Pressure Reducing Station	
	C. General	

Section No.	Subject	Page No.
	D. Site Issues and Layout	
	E. Masonry	
	F. Equipment	
	G. Conveying Systems	
	H. Mechanical	
	I. Electrical & Instrumentation	
29.	Treatment Plants	29-1
	A. Purpose	
	B. Abbreviations	
	C. Sewage Treatment Design and Operation	
	D. Solids Handling Design and Operation	
	E. Access to Unit Processes and Equipment	
	F. Sampling	
	G. Chemical Containment	
	H. Chemical Feed Systems	
	I. Drain Systems	
	J. Emergency Eyewash and Showers	
	K. Equipment Numbering Sequences	
	L. Equipment Spare Parts	
	M. Miscellaneous Items	
	N. Noise Abatement	
	O. Non-Potable Water Systems	
	P. Odor Control and Room Ventilation	
	Q. Pipe Insulation and Heat Tracing	
	R. Primary and Secondary Clarifiers	
	S. Process Air Piping	
	T. Process Flow Splitting	
	U. Scum Handling, Piping and Pumping	
	V. Grit, Septage and Grease, and Biosolids	
	W. Site Lighting	
	X. Slide and Sluice Gates	
	Y. Solids Piping	
	Z. Travel Path (Walkway) Alignment	
	AA. Yard Piping (Greater than 24 Inch in Diameter)	
	BB. Functional Descriptions	
	CC. Operational Technical Information System (OTIS)	
	DD. Equipment Startup, Training, and Turnover	
	EE. Flow Metering	
30.	Electrical and Instrumentation	30-1
	A. Introduction	
	B. General	

Section No.	Subject	Page No.
	C. Pump Station and Interceptor Systems Table	
	D. Treatment Plant Table	
	Exhibit A “HRSD Arc Flash Mitigation Workshop”	
	Exhibit B “Load Bank Connections”	
	Exhibit C “Variable Frequency Drive”	
	Exhibit D “HRSD Lighting Guidelines”	
	Exhibit E “HRSD Electric Motor Specifications”	
	Exhibit F “Stilling Well for Level Transducer Pumping Stations or Treatment Plants”	
	Exhibit G “Temporary Portable Pump Alarms and Setup Schedule”	
31.	Information Technology Infrastructure Hardware	31-1
	A. Introduction	
	B. General	
	C. Specific Requirements	
32.	Miscellaneous	32-1
	A. Introduction	
	B. Site	
	1. Site Drainage	
	2. Landscaping	
	3. Plant Material	
	4. Concrete Curb and Gutter	
	5. Sidewalks	
	C. Concrete	
	D. Masonry	
	E. Metals and Plastics	
	1. Hand / Guard Rails and Stair Systems	
	2. Hatches	
	3. Grating	
	F. Thermal and Moisture Protection	
	1. Roofing	
	G. Doors and Hardware	
	1. General	
	2. Pump Stations	
	3. Treatment Plants	
	H. Painting and Coatings	
	1. Painting and Coating Systems	
	2. Piping and Equipment Identification	
	3. Limits of Coatings in Covered Tanks	
	4. Pump Stations	
	I. Architectural / Structural	

Section No.	Subject	Page No.
33.	Standard for Capital Improvement Projects that Involve Construction Dewatering Activities	33-1
	A. Introduction	
	B. Background	
	C. Requirements	
	D. Receiving Sewer System	
	E. Contacts	
	Attachment A – Anticipated Schedule from Initial Investigation to General Permit Acquisition	A
	Attachment B – Contaminated Identification Table	B
34.	Standard Details	34-1
	A. Introduction	
	B. Listing of Standard Details	
	1. Series 100: Miscellaneous	
	100 - Standard Cover Sheet	
	101- Easement Plat	
	102 - Exterior Bollard Detail	
	103 - Bollard Location Detail	
	104 - Load Test Hinged Bank Box	
	105A/B - Flush-mount Groundwater Monitoring Well	
	106 - Recovery Sheet Template	
	2. Series 200: Collection Systems and Appurtenances	
	200A/B - Precast Concrete Manhole with Extended Monolithic Base	
	201 - Precast Concrete Shallow Manhole with Extended Base	
	202A/B - Sanitary Sewer Straddle Manhole	
	203 - Connection into Existing Manholes	
	204 - Manhole Invert Shaping	
	205 – Precast Concrete or Brick Manhole Inside Gravity Drop Connection to Existing Manhole	
	206 – Precast Concrete Outside Drop Manhole	
	207 - Precast Concrete or Brick Manhole Inside Force Main Drop Connection to Existing Manhole	
	208 – Precast Concrete Sanitary Sewer Manhole Adjustment	
	209 - Manhole Insert	
	226 – Stub-out Connection for Existing Manholes	
	227 - Standard Manhole Frame and Cover	
	228 - Manhole Frame and Cover – Watertight	
	229A/B – Sanitary Sewer Lateral Installation	
	230 – Sanitary Sewer Service Connection for New Developments	

Section No.	Subject	Page No.
	251 – Sanitary Sewer Service Clean Out Frame and Cover (Non-Traffic Rated)	
	252 – Sanitary Sewer Service Clean Out Frame and Cover (Traffic Rated)	
	253 – Tracer Wire Locator Box	
	276 – Vacuum Air Intake Valve	
	277 – Deactivation at HRSD Gravity Main	
	3. Series 300: Interceptors and Appurtenances	
	300 - Connection to Existing HRSD Valve (No Potential for Additional Development)	
	301 - Connection to Existing HRSD Valve (Additional Development Possible)	
	302 - Connection to Existing HRSD Valve (Additional Development Imminent)	
	303 – New Wet Taps (No Potential for Additional Development)	
	304 – New Wet Taps (Additional Development Possible)	
	305 – New Wet Taps (Additional Development Imminent)	
	306A – 2” Private Connection to Existing 2” HRSD Stub	
	306B – Valve Vault for 2” HRSD Valve	
	306C – Vault Lid for 2” HRSD Valve	
	307 – Lawnes Point Private Connection Detail	
	308 – Private Force Main to HRSD Asset	
	326 – Horizontal Gate Valve	
	327 – Vertical Gate Valve	
	328 - Valve Box and Riser for Mainline Tracer Wire Box	
	329 – Valve Box and Riser for Bypass Valves	
	330 – Valve Riser Adjustment	
	331A/B - Roadside Ditch – Valve Box	
	351 - Air Vent	
	352A/B - Air Release Valve Box Adjustment	
	353 - Roadside Ditch – Air Vent	
	354 - Air Vent Frame and Cover	
	376 - Tapping Saddle for Cast Iron Pipe, Ductile Iron, RC & PVC Pipe	
	377 - Tapping Saddle for Concrete Cylinder Pipe	
	378A/B - Steel Casing Pipe Detail	
	379 - Ductile Iron MJ Spigot to Concrete Transition Adaptor (Male)	
	380 - Ductile Iron MJ Spigot to Concrete Transition Adaptor (Female)	
	381 - Pressure Sensor Installation	
	382 – Concrete Cylinder Pipe Line Stop Detail	

Section No.	Subject	Page No.
	383 – Ductile / Cast Iron Line Stop Detail	
4.	Series 400: Pump Stations and PRS	
	400A/B – Small Communities Sample Design Detail – Submersible Pump Station	
	401A/B – Underground Storage Tank	
	402A/B – Underground Fuel Tank	
5.	Series 500: Cathodic Protection for Pipes	
	500 - Cathodic Protection Test Station	
	501 - Cathodic Protection Isolation Detail	
	502 – Anode Test Station	
	503 – Monitoring Test Station	
	504 – Monitoring Test Station (with Riser)	
	505 – Isolation Flange Test Station	
	506 – Isolation Flange Test Station (with Riser)	
	507 – Anode Header Cable Splice	
	508 – Thermite Weld	
	509 – Isolating Flange Kit	
	521 – Ductile Iron Pipe Galvanic System AC Ground Mat	
	522 – Ductile Iron Pipe Galvanic System Insulating Corporation	
	523 - Ductile Iron Pipe Galvanic System Main Bonding	
6.	Series 600: Cathodic Protection for Buildings	
	600 – Installation of Discrete Galvanic Anodes	
	601 – Installation of Distributed Galvanic Anodes	
	602 – Distributed Galvanic Anodes at Top of Wall	
	603 – Installation of Drilled-in Galvanic Anodes	
	604 – Conductive Mortar Bridge for use with High Resistivity Repair Mortars	
	605 – Typical Galvanic Anode Layout	
	606 – Typical Galvanic Anode Connections	
	626 – Removal of Unsound Concrete Typical Section	
	627 – Concrete Rebuild Typical Section	
	628 – Concrete Rebuild to Provide Minimum Cover Typical Section	
	629 – Removal of Unsound Concrete Typical Corner Section	
	630 – Concrete Rebuild Typical Corner Section	
	631 – Reinforcing Section Loss Table	
	632 – Lap Splice – Option 1	
	633 – Lap Splice Lengths – Option 1	
	634 – Mechanical Splice – Option 2 Typical Removal Section	
	635 – Mechanical Splice – Option 2 Typical Rebuild Section	
	636 – Weld Splice – Option 3	
	637 – Weld Splice Details – Option 3	

Section No.	Subject	Page No.
	638 – Weld Splice Details – Option 3	
	639 – Supplemental Reinforcement Requirements	
	640 – Adhesive Grouted Dowel Layout	
	641 – Typical Concrete Rebuild Section at Embed Plate	
	642 – Shallow Depth (2” Max) Concrete Rebuild Horizontal	
	643 - Shallow Depth (2” Max) Concrete Rebuild Vertical	
	644 – Partial Depth Core Hole Concrete Rebuild	
	645 – Full Depth Core Hole Concrete Rebuild	
	675 – Typical Sealant Details	
	Attachment A – Series 100 Details (PDF)	100
	Attachment B – Series 200 Details (PDF)	200
	Attachment C – Series 300 Details (PDF)	300
	Attachment D – Series 400 Details (PDF)	400
	Attachment E – Series 500 Details (PDF)	500
	Attachment F – Series 600 Details (PDF)	600
35.	Suggested Division 1 Items	35-1
	A. Introduction	
	B. Table of Division 1 Items for FIRM Consideration	
36.	Front End Documents	36-1
	A. Introduction	
	B. Responsibilities of the FIRM	
	C. Standard Front End Documents	
	1. Project Specification Cover	
	2. Table of Contents	
	3. Advertisement for Bids	
	4. Instruction to Bidders	
	5. Questionnaire	
	6. Bid Bond	
	7. Agreement	
	8. Performance Bond	
	9. Payment Bond	
	10. Escrow Agreement	
	11. General Conditions of the Construction Contract	
	12. Supplementary Conditions	
	D. Specific Documents Requiring FIRM Input	
	1. Advertisement for Bid	
	2. Instructions to Bidders	
	3. Agreement	
	4. Supplementary Conditions	
	Attachment A – EJCDC Front End Documents (PDF)	A

Section No.	Subject	Page No.
37.	Construction Administration Forms/Format	37-1
	A. Introduction	
	B. Contract Administration Forms	
	1. Sample Bid Recommendation Letter	
	2. Notice of Award	
	3. Notice to Proceed	
	4. Emergency Contact List	
	5. Field Order	
	6. Request for Proposal	
	7. Work Change Directive	
	8. Change Order	
	9. Application for Payment	
	a. Summary Sheet	
	b. Schedule of Values – Lump Sum	
	c. Schedule of Values – Unit Price	
	d. Stored Materials Inventory	
	e. Diversity Procurement Statement	
	10. Certificate of Substantial Completion	
	11. Warranty Memorandum	
	Attachment A – Notice of Award (PDF)	A
	Attachment B – Change Order Form (PDF)	B
	Attachment C – Application for Payment (PDF)	C
	Attachment D – Project Emergency Contact List Template	D
38.	Master Specification Sections Overview	38-1
	A. Introduction	
	B. Listing of Master Specification Sections	
	01010 – Summary of Work	
	01040 - Coordination	
	01060 – Special Conditions	
	01270 – Measurement and Payment	
	01323 – Record Documents	
	01340 – Submittals	
	01520 – Maintenance of Pipeline and Pumping Operations	
	01560 – Environmental Protection and Special Controls	
	01650 – Facility and System Start-up	
	02510 – Ductile Iron Pipe	
	02520 – Polyvinyl Chloride Pipe	
	02531 – Line Stops on Sanitary Sewer Force Main Systems	
	02610 – Valves	
	02710 – Contaminated Groundwater Management	
	02761 – Television Inspection of Pipelines	
	02773 – Ultrasonic Pipeline Inspection	

Section No.	Subject	Page No.
	02774 – Condition Assessment Data Collection for Pipelines Being Repaired Or To Be Abandoned	
	03700 – Concrete Rebuild	
	03800 – Embedded Galvanic Anodes for Concrete Rebuild	
	07160 – Reactive Waterproofing	
	07900 – Joint Sealants and Expansion Joint Systems	
	09900 – Protective Coatings	
	13110 – Cathodic Protection	
	Attachment A - 01010 – Summary of Work	01010
	Attachment B - 01040 - Coordination	01040
	Attachment C - 01060 – Special Conditions	01060
	Attachment D - 01270 – Measurement and Payment	01270
	Attachment E - 01323 – Record Documents	01323
	Attachment F - 01340 – Submittals	01340
	Attachment G - 01520 – Maintenance of Pipeline and Pumping Operations	01520
	Attachment H - 01560 – Environmental Protection and Special Controls	01560
	Attachment I - 01650 – Facility and System Start-up	01650
	Attachment J - 02510 – Ductile Iron Pipe	02510
	Attachment K - 02520 – Polyvinyl Chloride Pipe	02520
	Attachment L - 02531 – Line Stops on Sanitary Sewer Force Main Systems	02531
	Attachment M - 02610 – Valves	02610
	Attachment N - 02710 – Contaminated Groundwater Management	02710
	Attachment O - 02761 – Television Inspection of Pipelines	02761
	Attachment P - 02773 – Ultrasonic Pipeline Inspection	02773
	Attachment Q - 02774 – Condition Assessment Data Collection for Pipelines Being Repaired Or To Be Abandoned	02774
	Attachment R - 03700 – Concrete Rebuild	03700
	Attachment S - 03800 – Embedded Galvanic Anodes for Concrete Rebuild	03800
	Attachment T - 07160 – Reactive Waterproofing	07160
	Attachment U - 07900 – Joint Sealants and Expansion Joint Systems	07900
	Attachment V - 09900 – Protective Coatings	09900
	Attachment W - 13110 – Cathodic Protection	13110