

Army Base Treatment Plant

24.

Photo Credit: J Zimba







System: Army Base Type: Pipelines Army Base 24-Inch and 20-Inch Transmission Main Replacements

PR_AB010000

Driver Category: I&I Abatement-Rehabilitation Plan Project Phase: Design Regulatory: Rehab Plan Phase Two

\$16,15<u>3,907</u>

Est. Project Costs

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30	FY31	FY32
\$14,284	\$1,643	\$4,324	\$7,095	\$1,216	\$7	\$0	\$0	\$0	\$0	\$0	\$0


PROJECT DESCRIPTION

This project is to study, design and construct a replacement interceptor for Line SF-004, 24-inch cast iron pipe and 20-inch cast iron pipe and Line SF-005, 20-inch reinforced concrete pipe from Baker Street to Newport Avenue, approximately 4,650 linear feet (LF). A single line is planned to replace these twin lines along the current alignment. This single pipeline is planned to be 36-inch in the Regional Wet Weather Management Plan. The original scope of the CIP included an additional 13,000 LF of pipeline replacement from Newport Avenue to Simons Drive. At this time, condition assessment of this additional pipe is only planned in an effort to prioritize funds on the highest risk assets. This project also includes abandoning a portion of line SG-003, a section of gravity pipe from MH-SG-003-3889 to MH-SG-003-3747 at the intersection of Baker Street and Hampton Boulevard that is not in service and is deteriorating.

PROJECT JUSTIFICATION

This project will address specific sections of SF-004 that was designed and built in 1956 according to the plans inherited from the City of Norfolk. The same plans show an existing 20-inch concrete line, now HRSD line number SF-005. Since SF-005 was turned over to HRSD in 1956, it is at least 50 years old. Both lines have multiple repairs installed by HRSD and repair history prior to HRSD ownership is unknown. Multiple branch valves along this alignment are 1948 or 1956 valves that are difficult to repair or get replacement parts. The valve guide AB-2005 area will be included in the condition assessment portion of the CIP. This area has several valves indicated as inoperable and an abandoned dead-end section of pipe. These lines are the main interceptors conveying wastewater from the City of Norfolk to the Army Base Treatment Plant. This project also includes abandoning the gravity line SF-002. Flow is currently bypassing this section of pipe and the pipe is in poor condition from tuberculation and infiltration.

FUNDING TYPE		CONTACTS	
Funding Type:	Revenue Bond	Contacts-Requesting Dept: Contacts-Dept Contacts: Contacts-Managing Dept:	Operations-Interceptors Holly Anne Matel Engineering
PROPOSED SCH	IEDULE START DATE	COST ESTIMATE	
PrePlanning PER Design Delay Design Bid Delay PreConstruction Construction Closeout	11/01/2012 06/03/2013 12/03/2013 04/01/2021 09/01/2022 09/01/2022 12/01/2022 09/01/2024	Closeout	Class 3 \$0 \$158,936 \$1,630,671 \$30,000 \$12,424,300 \$40,000 \$14,283,907 \$1,870,000





System: Army Base Type: Pipelines Driver Category: Aging Infrastructure/Rehabilitation Project Phase: Design Regulatory: None

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30	FY31	FY32
\$1,606	\$184	\$487	\$788	\$144	\$3	\$0	\$0	\$0	\$0	\$0	\$0

PROJECT DESCRIPTION

This project is to study, design and construct a replacement interceptor for Line SF-006, approximately 2,642 linear feet (LF) of 10-inch cast iron force main that is the discharge line from HRSD Pump Station #117 (North Shore Road). This project will include replacement main line valves, branch valves, associated appurtenances and replace the existing force main through the walls into the pump station. HART analysis has determined that this force main will be downsized from 10-inch to 8-inch.

PROJECT JUSTIFICATION

This project will replace the cast iron force main that was installed in 1948. There have been two documented repairs in 1964 and in 2005. Operations staff believes that there are additional undocumented repairs on the line, as well. The pipeline is of a material and age for which HRSD has seen recent repeated failures in other parts of the interceptor system due to wastewater chemistry and soil corrosion.

FUNDING TYPE		CONTACTS	
Funding Type:	Revenue Bond	Contacts-Requesting Dept: Contacts-Dept Contacts: Contacts-Managing Dept:	Operations-Interceptors Holly Anne Matel Engineering
PROPOSED SCH	IEDULE START DATE	COST ESTIMATE	
PrePlanning PER Design Delay Design Bid Delay PreConstruction Construction Closeout	11/01/2012 06/03/2013 12/03/2013 04/01/2021 09/01/2022 09/11/2022 12/01/2022 09/01/2024	Cost Estimate Class: PrePlanning PER Design PreConstruction Construction Closeout Est. Program Cost Contingency Budget Est. Project Costs	Class 3 \$0 \$19,644 \$181,136 \$10,000 \$1,380,530 \$15,000 \$1,606,310 \$208,000 \$1,814,310





System: Army Base Type: SWIFT Driver Category: I&I Abatement-IP/RWWMP Project Phase: Proposed Regulatory: Integrated Plan-SWIFT

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30	FY31	FY32
\$44,169	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$16,895	\$27,275


PROJECT DESCRIPTION

This project will construct a new pump station and force main to convey treated secondary clarifier effluent from Army Base Treatment Plant to the Virginia Initiative Plant (VIP) for further treatment in a combined SWIFT facility. The proposed firm capacity of the pump station is 15.6 million gallons per day (MGD). The proposed force main is estimated to be 30 inch diameter. The proposed route requires the use of multiple installation methods, including conventional trenching, horizontal direct drilling across the Lafayette River, and micro-tunneling underneath the Norfolk Marine Terminal railroad tracks. The location of this pump station has not been identified. The scope of the project does not include property or easement acquisition, equalization tank construction, or treatment process upgrades.

PROJECT JUSTIFICATION

Implementation of full scale SWIFT treatment at HRSD wastewater treatment plants discharging to the James River is needed to reduce nutrients entering the Chesapeake Bay, augment the groundwater supply, reduce the rate of ground subsidence, protect groundwater from saltwater intrusion, and support Virginia's economy. The SWIFT master planning effort has determined that advanced water treatment and aquifer recharge at Army Base has significant physical limitations including site availability. This project would support the capture and further advanced treatment of Army Base secondary clarifier effluent in a consolidated SWIFT treatment facility located adjacent to VIP.

FUNDING TYPE		CONTACTS	
Funding Type:	WIFIA	Contacts-Requesting Dept: Contacts-Dept Contacts: Contacts-Managing Dept:	Engineering Lauren Zuravnsky Engineering
PROPOSED SC	HEDULE START DATE	COST ESTIMATE	
PrePlanning PER Design Delay Design Bid Delay PreConstruction Construction Closeout	07/01/2030 09/01/2030 12/01/2030 12/01/2030 08/01/2031 08/01/2031 10/01/2031 03/01/2033	PreConstruction Construction \$ Closeout Est. Program Cost \$	\$0 \$857,900 \$1,421,600 \$50,000 47,600,000 <u>\$0</u> 49,929,500 \$9,800,000
		Est. Project Costs \$	59,729,500



HRSD

WTP HRSD Treatment Plant

PS HRSD Pump Station

RS HRSD Pressure Reducing Station



Army Base Treatment Plant Administration Building Renovation (2021)

System: Type: Army Base Facilities, Buildings and Capital Equipment

Driver Category:Aging Infrastructure/RehabilitationProject Phase:PERRegulatory:None

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30	FY31	FY32
\$1,666	\$142	\$926	\$591	\$7	\$0	\$0	\$0	\$0	\$0	\$0	\$0


PROJECT DESCRIPTION


This project is to renovate the existing administration building at the Army Base Treatment Plant.

PROJECT JUSTIFICATION

This project will provide additional administration offices, lunch room, conference room, lab and control area, women and unisex bathrooms.

FUNDING TYPE		CONTACTS	
Funding Type:	Revenue Bond	Contacts-Requesting Dept: Contacts-Dept Contacts: Contacts-Managing Dept:	Operations-Treatment Tim Marsh Engineering
PROPOSED SCH	EDULE START DATE	COST ESTIMATE	
PrePlanning PER Design Delay Design Bid Delay PreConstruction Construction Closeout	07/01/2020 02/01/2021 12/01/2021 04/01/2022 10/01/2022 10/01/2022 01/01/2023 11/01/2023	Cost Estimate Class: PrePlanning PER Design PreConstruction Construction Closeout Est. Program Cost Contingency Budget Est. Project Costs	\$0 \$49,837 \$146,779 \$5,000 \$1,444,052 \$20,000 \$1,665,668 \$346,003 \$2,011,671







System: Type: Army Base Pump Stations Driver Category: Aging Infrastructure/Rehabilitation Project Phase: Pre Planning Regulatory: None

PROGRAM CASH FLOW PROJECTION (\$,000)

	Exp to										
Prog Cost	Previous Year	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30	FY31	FY32
\$6,010	\$0	\$1,450	\$2,880	\$1,680	\$0	\$0	\$0	\$0	\$0	\$0	\$0

PROJECT DESCRIPTION

This project will build an HRSD wastewater pumping station to replace a City of Norfolk wastewater pumping station (#27) at the intersection of Granby Street and North Shore Road. Norfolk will be funding the design of this project with their contract with Michael Baker, Inc. and will be providing \$2 million for design and some construction. HRSD will perform gravity sewer installation, which will become a Norfolk asset, from the existing Norfolk Pump Station (PS) #27 to the proposed HRSD Wards Corner PS. The HRSD PS will be located in the adjacent to the Norfolk PS #27, which will also become HRSD's PS to be demolished. The existing force main (FM) which is currently the City of Norfolk's PS #27, which currently connects to SF-005 at the intersection of Newport Avenue and Bradford Avenue will become an HRSD FM. Connection work will be required at Newport Avenue and Burleigh Avenue.

PROJECT JUSTIFICATION

HRSD and the City of Norfolk Department of Utilities collaborated and agreed that the existing City PS #27 would best be owned and operated by HRSD as a terminal pump station. Norfolk Utilities had hired the firm of Michael Baker several years ago to replace the existing PS #27 with a new station that was to be designed and built to Norfolk standards upon property acquired by the City. Upon recent conversations and desired direction from both HRSD and Norfolk Utilities, the firm of Michael Baker will remain engaged for design of the new station to HRSD standards. HRSD and Norfolk are entering into both a Cost Sharing Agreement related to the design and construction of this new pump station and an Asset Transfer Agreement for HRSD to take on ownership and operation of the existing City PS #27 until such time as the new replacement pump station is online and the previous pump station abandoned and demolished.

FUNDING TYPE		CONTACTS	
Funding Type:	Revenue Bond	Contacts-Requesting Dept: Contacts-Dept Contacts: Contacts-Managing Dept:	Engineering Phil Hubbard Engineering
PROPOSED SC	HEDULE START DATE	COST ESTIMATE	
PrePlanning PER	01/01/2021	Cost Estimate Class: PrePlanning	Class 4 \$0

PER	01/01/2021
Design Delay	06/01/2021
Design	11/02/2021
Bid Delay	10/01/2022
PreConstruction	10/02/2022
Construction	01/02/2023
Closeout	02/02/2025

Cost Estimate Class:	Class 4
PrePlanning	\$0
PER	\$0
Design	\$0
PreConstruction	\$10,000
Construction	\$6,000,000
Closeout	\$0
Est. Program Cost	\$6,010,000
Contingency Budget	\$2,000,000
Est. Project Costs	\$8.010.000