# Chesapeake-Elizabeth Treatment Plant

Photo Credit: J Cook

and white have









Birchwood Trunk 24-Inch and 30-Inch FM at Independence BIvd Replacement Ph II

PR\_CE011300

System: Type: Chesapeake-Elizabeth Pipelines Driver Category: I&I Abatement-Rehabilitation Plan Project Phase: Proposed Regulatory: Rehab Plan Phase Two

## **PROGRAM CASH FLOW PROJECTION (\$,000)**

Prog Cost	Exp to Previous Year	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30	FY31	FY32
\$1,720	\$120	\$591	\$1,003	\$7	\$0	\$0	\$0	\$0	\$0	\$0	\$0

## PROJECT DESCRIPTION

This project will replace approximately 350 linear feet of 24-inch reinforced concrete (RC) force main crossing Independence Boulevard just south of Cleveland Street in the City of Virginia Beach.

## **PROJECT JUSTIFICATION**

In December 2009, a leak was identified on line SF-120 in Independence Boulevard just south of the abandoned railroad tracks south of Cleveland Street. The leak was excavated and repaired under an emergency declaration. As a precaution, in the event the repair fails, URS Corporation was commissioned to develop 60 percent plans to replace the existing force main. This CIP provides for the completion of bid ready plans, specifications and includes the cost of construction to replace the existing force main in its entirety via horizontal directional drill across Independence Boulevard.

FUNDING TYPE		CONTACTS		
Funding Type:	Revenue Bond	Contacts-Requesting Dept: Contacts-Dept Contacts: Contacts-Managing Dept:	Engineering Tim Marsh Engineering	
PROPOSED SC	HEDULE START DATE	COST ESTIMATE		
PrePlanning PER Design Delay Design Bid Delay PreConstruction Construction Closeout	09/01/2010 11/28/2021 05/29/2022 05/29/2022 12/28/2022 12/28/2022 03/29/2023 03/29/2023	Cost Estimate Class: PrePlanning PER Design PreConstruction Construction Closeout Est. Program Cost Contingency Budget	\$0 \$85,400 \$120,000 \$5,000 \$1,500,000 \$10,000 <b>\$1,720,400</b> \$344,080	
		Est. Project Costs	\$2,064,480	





Poplar Hall Davis Corner Trunk 24-Inch Gravity Sewer Improvements

PR\_CE011600

System: Type: Chesapeake-Elizabeth Pipelines Driver Category:I&I Abatement-Rehabilitation PlanProject Phase:ProposedRegulatory:Rehab Plan Phase Two

# **PROGRAM CASH FLOW PROJECTION (\$,000)**

Prog Cost	Exp to Previous Year	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30	FY31	FY32
\$2,052	\$104	\$288	\$1,651	\$9	\$0	\$0	\$0	\$0	\$0	\$0	\$0

## **PROJECT DESCRIPTION**

This project is to rehabilitate and/or replace 1600 linear feet of gravity pipeline with associated manholes. Pipe diameter is 24-inches. Project extents are from: (1) MH-SG-113-1543 to SS-PS-115-1 and (2) MH-SG-113-4219 to MH-SG-113-3961

# **PROJECT JUSTIFICATION**

Condition assessment activities indicate that these assets present a material risk of failure due to physical condition defects.

FUNDING TYPE		CONTACTS	
Funding Type:	Revenue Bond	Contacts-Requesting Dept: Contacts-Dept Contacts: Contacts-Managing Dept:	Operations-Interceptors Tim Marsh Engineering
PROPOSED SC	HEDULE START DATE	COST ESTIMATE	
PrePlanning PER Design Delay Design Bid Delay PreConstruction Construction Closeout	03/01/2021 11/28/2021 05/29/2022 05/29/2022 03/29/2023 03/29/2023 06/28/2023 06/27/2024	Cost Estimate Class: PrePlanning PER Design PreConstruction Construction <u>Closeout</u> Est. Program Cost	Class 4 \$0 \$72,200 \$160,000 \$10,000 \$1,800,000 \$10,000 \$2,052,200
		Contingency Budget	\$412,440
		Est. Project Costs	\$2,464,640







Chesapeake-Elizabeth Treatment Plant Decommissioning

System: Type: Chesapeake-Elizabeth Strategic Planning Driver Category: Risk Mitigation Project Phase: Proposed Regulatory: None

## **PROGRAM CASH FLOW PROJECTION (\$,000)**

Prog Cost	Exp to Previous Year	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30	FY31	FY32
\$11,497	\$222	\$2,229	\$5,529	\$3,517	\$0	\$0	\$0	\$0	\$0	\$0	\$0

## PROJECT DESCRIPTION

This project will study and demolish or abandon facilities at the Chesapeake-Elizabeth Treatment Plant (CETP) Site. This project will also look at other potential uses for this site after the plant has been decommissioned.

Demolishment or abandonment needed at CETP may include, but is not limited to, aeration tanks, clarifiers, preliminary treatment facility, incinerator building, thickeners, chlorine contact tanks, pump stations, yard piping, and outfalls. Refer to HRSD CETP Wet Weather Storage Facility Conversion Technical Memo for additional information.

## **PROJECT JUSTIFICATION**

The Chesapeake-Elizabeth Treatment Plant Feasibility Study completed by HRSD in October 2013 evaluated taking the treatment plant offline and diverting flow to other treatment plants. The study determined that the HRSD interceptor system and remaining treatment plants have the ability to serve the current and projected needs of the South Shore jurisdictions when the Chesapeake-Elizabeth Treatment Plant would be taken offline in 2021. Significant capital and operation and maintenance (O&M) savings from this decision results in a high net present value compared to the former strategy.

FUNDING TYPE		CONTACTS	
Funding Type:	Revenue Bond	Contacts-Requesting Dept: Contacts-Dept Contacts: Contacts-Managing Dept:	Operations-Treatment Jeff Layne Engineering
PROPOSED SC	HEDULE START DATE	COST ESTIMATE	
PrePlanning PER Design Delay Design Bid Delay PreConstruction Construction Closeout	07/03/2017 01/01/2022 06/01/2022 08/01/2022 04/01/2023 04/01/2023 08/01/2023 02/01/2025	Cost Estimate Class: PrePlanning PER Design PreConstruction Construction Closeout Est. Program Cost Contingency Budget	Class 5 \$0 \$222,418 \$2,221,306 \$10,000 \$9,043,061 \$0 \$11,496,785
		Est. Project Costs	\$11,496,785







System: Atlantic Type: Pump Stations PR\_CE011827

Driver Category: Performance Upgrades Project Phase: Closeout Regulatory: Nutrient Reduction

# **PROGRAM CASH FLOW PROJECTION (\$,000)**

Prog Cost	Exp to Previous Year	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30	FY31	FY32
\$9,066	\$8,762	\$304	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

## PROJECT DESCRIPTION

This project is to make reliability improvements to the existing Atlantic Pressure Reducing Station (PRS), including new pumps, interior piping and valves, electrical system, controls, and access platforms. Structural, yard piping and valve, and mechanical modifications are also included. Interior building modifications to isolate and protect sensitive electrical equipment are also proposed. This project must be substantially complete by June 2021.

#### **PROJECT JUSTIFICATION**

The project is needed to ensure reliable operation of this PRS in support of the planned Chesapeake-Elizabeth Treatment Plant closure and diversion of flow to the Atlantic Treatment Plant and for the ultimate Regional Wet Weather Management Plan (RWWMP). This PRS will run daily after the CETP closure and improvements to the pumping and supporting equipment are required to address persistent pump ragging issues that currently hinder operation.

FUNDING TYPE		CONTACTS		
Funding Type:	Revenue Bond	Contacts-Requesting Dept: Contacts-Dept Contacts: Contacts-Managing Dept:	Engineering Laura Kirkwood Engineering	
PROPOSED SCI	HEDULE START DATE	COST ESTIMATE		
PrePlanning PER Design Delay Design Bid Delay PreConstruction Construction Closeout	03/01/2017 06/01/2017 03/01/2018 03/01/2018 04/01/2019 04/01/2019 02/01/2020 07/01/2022	Cost Estimate Class: PrePlanning PER Design PreConstruction Construction Closeout Est. Program Cost Contingency Budget	Class 1 \$0 \$196,920 \$723,159 \$15,421 \$7,811,344 \$318,800 <b>\$9,065,644</b> \$30,000	
		Est. Project Costs	\$9,095,644	



PS HRSD Pump Station

Virginia Beach



System: Atlantic Type: Pump Stations Driver Category: Performance Upgrades Project Phase: Closeout Regulatory: Nutrient Reduction

# **PROGRAM CASH FLOW PROJECTION (\$,000)**

Prog Cost	Exp to Previous Year	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30	FY31	FY32
\$4,957	\$4,863	\$94	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

## PROJECT DESCRIPTION

This project is to make reliability improvements to the existing Kempsville Pressure Reducing Station (PRS), including new pumps, interior piping and valves, electrical system, generator, controls, and access platforms. Interior building modifications to isolate and protect sensitive electrical equipment are also proposed. This project must be substantially complete by June 2021.

## **PROJECT JUSTIFICATION**

The project is needed to ensure reliable operation of this PRS in support of the planned Chesapeake-Elizabeth Treatment Plant closure and diversion of flow to the Atlantic Treatment Plant. This PRS will run daily after the CETP closure and improvements to the pumping and supporting equipment are required to address persistent pump ragging issues that currently hinder operation.

FUNDING TYPE		CONTACTS		
Funding Type:	Revenue Bond	Contacts-Requesting Dept: Contacts-Dept Contacts: Contacts-Managing Dept:	Engineering Laura Kirkwood Engineering	
PROPOSED SC	HEDULE START DATE	COST ESTIMATE		
PrePlanning PER Design Delay Design Bid Delay PreConstruction Construction	03/01/2017 06/01/2017 04/01/2018 04/01/2018 04/01/2019 04/01/2019 09/01/2019	Cost Estimate Class: PrePlanning PER Design PreConstruction Construction Closeout	Class 1 \$0 \$170,501 \$505,760 \$15,421 \$4,150,507 \$114,675	
Closeout	07/01/2022	Est. Program Cost Contingency Budget	<b>\$4,956,864</b> \$9,000	
		Est. Project Costs	\$4,965,864	





Virginia Beach City Pump Station Upgrades, Phase V

PR\_CE011835

System: Type: Chesapeake-Elizabeth Locality and Private Property Driver Category: Capacity Improvements Project Phase: Construction Regulatory: Nutrient Reduction

# **PROGRAM CASH FLOW PROJECTION (\$,000)**

Prog Cost	Exp to Previous Year	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30	FY31	FY32
\$1,613	\$363	\$1,250	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

## PROJECT DESCRIPTION

This project is to complete upgrades on City of Virginia Beach Pump Stations that cannot meet the new pressure policy post-2021. Pump Stations 309 (Lake Front Village) and 310 (Lake Shores West) are included in this effort. HRSD completed a Preliminary Engineering Study in 2018. The City of Virginia Beach will administer design and construction with reimbursement from HRSD for the required upgrades. All betterments to the stations will be paid for by the City.

## **PROJECT JUSTIFICATION**

The project is needed to ensure that the Virginia Beach pump stations can meet HRSD pressure policy when flow is diverted in support of the Chesapeake-Elizabeth Treatment Plant closure. This project was part of the Chesapeake-Elizabeth offline solution set developed by HRSD, CDM Smith, and Brown and Caldwell assuming a 2-year level of service.

FUNDING TYPE		CONTACTS		
Funding Type:	Cash	Contacts-Requesting Dept: Contacts-Dept Contacts: Contacts-Managing Dept:	Engineering Laura Kirkwood Engineering	
PROPOSED SC	HEDULE START DATE	COST ESTIMATE		
PrePlanning PER Design Delay Design Bid Delay PreConstruction Construction Closeout	03/01/2017 04/01/2017 06/01/2017 02/01/2018 01/01/2020 10/01/2020 05/01/2021 05/01/2022	Cost Estimate Class: PrePlanning PER Design PreConstruction Construction Closeout Est. Program Cost	Class 1 \$0 \$112,424 \$0 \$980 \$0 \$1,500,000 \$1,613,404	
		Est. Project Costs	\$150,000 \$1.763.404	







System: Type: Chesapeake-Elizabeth Locality and Private Property Driver Category: Capacity Improvements Project Phase: Design Regulatory: Nutrient Reduction

# **PROGRAM CASH FLOW PROJECTION (\$,000)**

Prog Cost	Exp to Previous Year	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30	FY31	FY32
\$706	\$118	\$588	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

## PROJECT DESCRIPTION

This project is to complete upgrades on the City of Norfolk Pump Station 124 (Airport PS) that cannot meet the new pressure policy post-2021. HRSD completed a Preliminary Engineering Study in 2018. The City of Norfolk will administer design and construction with reimbursement from HRSD for the required upgrades. All betterments to the station will be paid for by the City.

## PROJECT JUSTIFICATION

This project is needed to ensure that the City of Norfolk Pump Station 124 can meet HRSD pressure policy when flow is diverted in support of the Chesapeake-Elizabeth Treatment Plant closure.

FUNDING TYPE		CONTACTS					
Funding Type:	Cash	Contacts-Requesting Dept: Contacts-Dept Contacts: Contacts-Managing Dept:	Engineering Laura Kirkwood Engineering				
PROPOSED SC	HEDULE START DATE	COST ESTIMATE					
PrePlanning PER Design Delay Design Bid Delay PreConstruction Construction Closeout	09/01/2016 11/01/2017 01/01/2018 01/01/2020 01/01/2021 05/01/2021 05/01/2021	Cost Estimate Class: PrePlanning PER Design PreConstruction Construction Closeout Est. Program Cost	Class 1 \$0 \$0 \$0 \$688 \$0 \$705,000 <b>\$705,688</b>				
0.00000	00/01/2022	Contingency Budget	\$70,000				
		Est. Project Costs	\$775,688				



System: Type: Chesapeake-Elizabeth Locality and Private Property Driver Category: Capacity Improvements Project Phase: Pre Planning Regulatory: Nutrient Reduction

# **PROGRAM CASH FLOW PROJECTION (\$,000)**

Prog Cost	Exp to Previous Year	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30	FY31	FY32
\$1,434	\$819	\$615	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

## PROJECT DESCRIPTION

This project will complete upgrades on private pump stations that cannot meet the new pressure policy when the Chesapeake-Elizabeth Treatment Plant is closed and all flow is diverted to the Atlantic Treatment Plant at the end of calendar year 2021. Approximately 60 pump stations have been identified as potential at-risk stations. HRSD and their consultant will gather more information about these stations to determine improvements needed, such as changing out pumps or pump components. HRSD will work with local maintenance service providers to make improvements now through the end of 2022 after the diversion has been implemented for up to one year. In 2021, six stations were identified as requiring improvements.

## **PROJECT JUSTIFICATION**

The project is needed to ensure that private pump stations can meet HRSD pressure policy when flow is diverted in support of the Chesapeake-Elizabeth Treatment Plant closure.

FUNDING TYPE		CONTACTS				
Funding Type:	Cash	Contacts-Requesting Dept: Contacts-Dept Contacts: Contacts-Managing Dept:	Engineering Laura Kirkwood Engineering			
PROPOSED SCI	HEDULE START DATE	COST ESTIMATE				
PrePlanning PER Design Delay Design Bid Delay PreConstruction Construction Closeout	05/03/2021 05/31/2021 07/19/2021 08/01/2021 04/01/2022 04/01/2022 04/01/2022 01/01/2023	Cost Estimate Class: PrePlanning PER Design PreConstruction Construction Closeout Est. Program Cost Contingency Budget Est. Project Costs	Class 2 \$0 \$288 \$500,000 \$695 \$933,000 \$0 \$1,433,983 \$66,712 \$1,500,695			





Atlantic Service Area Automated Diversion Facilities Ph

PR\_CE011850

System: Type: Chesapeake-Elizabeth Pipelines

I

Driver Category: Performance Upgrades Project Phase: Construction Regulatory: None

**PROGRAM CASH FLOW PROJECTION (\$,000)** 

Prog Cost	Exp to Previous Year	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30	FY31	FY32
\$2,171	\$2,089	\$24	\$24	\$24	\$12	\$0	\$0	\$0	\$0	\$0	\$0

## **PROJECT DESCRIPTION**

The project will involve installing a new control valve at Lynn Shores Drive and adding control to an existing valve near North Hessian Road in Virginia Beach to provide greater operational flexibility and system diversion capabilities during wet weather events when flow from Chesapeake-Elizabeth Treatment Plant is diverted.

## **PROJECT JUSTIFICATION**

The project will include near real-time communication and control logic between multiple remote and pump station sites. The new controlled facilities will adapt to variable system conditions in order to maximize capacity of the existing interceptor system infrastructure. The project also reduces risk by providing a reliable means of isolation in the event of an emergency.

FUNDING TYPE		CONTACTS				
Funding Type:	Revenue Bond	Contacts-Requesting Dept: Contacts-Dept Contacts: Contacts-Managing Dept:	Operations-Interceptors Laura Kirkwood Engineering			
PROPOSED SC	HEDULE START DATE	COST ESTIMATE				
PrePlanning PER Design Delay Design Bid Delay PreConstruction Construction Closeout	10/01/2019 10/29/2019 12/18/2019 08/26/2020 11/27/2020 08/06/2021 09/16/2021 07/14/2022	Cost Estimate Class: PrePlanning PER Design PreConstruction Construction Closeout Est. Program Cost Contingency Budget Est. Project Costs	\$229,400 \$57,900 \$196,877 \$4,665 \$1,600,000 \$82,400 <b>\$2,171,241</b> \$160,000 <b>\$2.331.241</b>			





Witchduck Rd IFM Improvements

System: Type: Chesapeake-Elizabeth Pipelines Driver Category: Risk Mitigation Project Phase: Proposed Regulatory: None

## **PROGRAM CASH FLOW PROJECTION (\$,000)**

Prog Cost	Exp to Previous Year	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30	FY31	FY32
\$7,017	\$0	\$90	\$480	\$0	\$30	\$3,348	\$3,069	\$0	\$0	\$0	\$0

## **PROJECT DESCRIPTION**

This project will rehabilitate or replace 4,300 linear feet (LF) of 24-inch cast iron interceptor force main (IFM) (SF-121) along Witchduck Road between the Witchduck Road-Southern Boulevard and Bonnie Road intersections.

## **PROJECT JUSTIFICATION**

After the closure of the Chesapeake-Elizabeth Treatment Plant (CETP), the 1968-vintage cast iron force main along Witchduck Road will see additional service area and will need to stay in service for the foreseeable future to send flow to the Providence Tank and Pressure Reducing Station (PRS). In addition, the Witchduck corridor is seeing significant re-development by the City of Virginia Beach, therefore reliability of this line is essential. Based on a risk assessment performed by the Condition Assessment Department, this pipeline had the second highest criticality score of all force mains within the CETP closure area. Historically, cast iron pipelines have the highest likelihood of failing; at over 50 years old this pipeline is nearing the end of its useful life.

FUNDING TYPE		CONTACTS	
Funding Type:	VCWRLF	Contacts-Requesting Dept: Contacts-Dept Contacts: Contacts-Managing Dept:	Operations-Interceptors Jeff Scarano Engineering
PROPOSED SCI	HEDULE START DATE	COST ESTIMATE	
PrePlanning PER Design Delay Design Bid Delay PreConstruction Construction Closeout	06/01/2023 06/29/2023 08/18/2023 04/26/2024 07/30/2024 04/08/2026 07/08/2026 06/15/2028	Cost Estimate Class: PrePlanning PER Design PreConstruction Construction Closeout Est. Program Cost Contingency Budget Est. Project Costs	Class 5 \$0 \$180,000 \$390,000 \$30,000 \$6,417,000 \$0 <b>\$7,017,000</b> \$1,400,000 <b>\$8,417,000</b>