


Boat Harbor Treatment Plant



Photo Credit: VDOT



Legend

-  Boat Harbor Treatment Plant
-  CIP Interceptor Point
-  CIP Pump Station Point
-  CIP Interceptor Line
-  CIP Abandonment
-  Treatment Plant Service Area
-  HRSD Interceptor Force Main
-  HRSD Interceptor Gravity Main
-  HRSD Treatment Plant
-  HRSD Pressure Reducing Station
-  HRSD Pump Station

0 2,000 4,000 8,000 12,000 16,000 Feet

Boat Harbor Treatment Plant Service Area CIP Projects

Treatment Plant Projects

BH015700
GN016346



CIP Location



Service Area



BH013020

- Project Interceptor Line
- Project Interceptor Point
- Project Location Point
- Project Area

Legend

- CIP Interceptor Point
- CIP Pump Station Point
- CIP Interceptor Line
- CIP Abandonment
- CIP Project Area
- HRSD Interceptor Force Main
- HRSD Interceptor Gravity Main
- HRSD Treatment Plant
- HRSD Pressure Reducing Station
- HRSD Pump Station

0 25 50 100 150 200 Feet

BH013020

Willard Avenue Pump Station Replacement



CIP Location



System: Boat Harbor
Type: Pump Stations

Driver Category: Capacity Improvements
Project Phase: Construction
Regulatory: None

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$17,135	\$16,289	\$845	\$1	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

PROJECT DESCRIPTION

This project includes the replacement of the Willard Avenue Pump Station (PS) to address conditional issues. The proposed replacement will include a relocated pump station and new gravity and force main connections to the existing systems.

PROJECT JUSTIFICATION

This project will improve pump station capacity for the service area and reduce operation and maintenance demands. The existing Willard Avenue Pump Station is located at 219 National Avenue in Hampton, Virginia. The Station serves portions of Buckroe, Woodland and Phoebus including Fort Monroe and receives flow from multiple City Pump Stations and the HRSD Bay Shore Lane Pump Station. Flows can be diverted from the York River WWTP collection system to the Willard Avenue Pump Station through a valved connection at the HRSD Woodland Road Pump Station. The station discharges flows through a 30-inch force main to a gravity sewer manhole in downtown Hampton. A new force main is planned to realign the Hampton Trunk Sewer Extension Divisions I & J Phase II to remove the pipeline from the Hampton University campus. A new pump station will accommodate a wide range of wet weather flows as well as offer operational flexibility during dry weather periods. The following items are justification for completing this project: The existing pump station was constructed in 1944 and is nearing the end of its anticipated useful life. The existing pump station parcel is only 0.14 acres, which does not allow for any expansion and does not meet our current parcel size standards for a new pump stations site. Furthermore, building a new pump station at this location will be challenging given the close proximity to residents. HRSD will need to acquire a new parcel in the vicinity of the existing PS to build a new one. Upon completion of the new PS, the existing PS will be demolished and the parcel transferred or sold.

FUNDING TYPE

Funding Type: VCWRLF

CONTACTS


Contacts-Requesting Dept: Operations-Interceptors
Contacts-Dept Contacts: Ted Denny
Contacts-Managing Dept: Engineering

PROPOSED SCHEDULE START DATE

PrePlanning	01/01/2019
PER	05/01/2019
Design Delay	09/16/2019
Design	09/16/2019
Bid Delay	02/25/2022
PreConstruction	02/25/2022
Construction	07/01/2022
Closeout	08/01/2025

COST ESTIMATE

Cost Estimate Class:	Class 1 (-3% to +15%)
PrePlanning	\$2,030
PER	\$102,410
Design	\$1,341,931
PreConstruction	\$13,390
Construction	\$15,660,000
Closeout	\$15,000
Est. Program Cost	\$17,134,762
Contingency Budget	\$800,000
Est. Project Costs	\$17,934,762



- BH014220**
- Project Interceptor Line
 - Project Interceptor Point
 - Project Location Point
 - Project Area
- Legend**
- CIP Interceptor Point
 - CIP Pump Station Point
 - CIP Interceptor Line
 - CIP Abandonment
 - CIP Project Area
 - HRSD Interceptor Force Main
 - HRSD Interceptor Gravity Main
 - HRSD Treatment Plant
 - HRSD Pressure Reducing Station
 - HRSD Pump Station

0 360 720 1,440 2,160 2,880 Feet

BH014220

**Hampton Trunk Sewer Extension Divisions I and J
Relocation Phase II**



CIP Location





Hampton Trunk Sewer Extension Divisions I and J Relocation Phase II

PR_BH014220

System: Boat Harbor
Type: Pipelines

Driver Category: Relocation
Project Phase: Construction
Regulatory: None

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$17,238	\$16,526	\$707	\$5	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

PROJECT DESCRIPTION

This project includes the replacement of 7,500 linear feet (LF) of 30-inch force main (FM) from the new Willard Avenue Pump Station (PS) with 6,800 LF of new 24-inch FM. The new force main will originate from the new Willard Avenue PS to the connection at E. Queen Street and Eaton Street. The location of the new Willard Avenue PS is still pending and may impact the alignment of the FM. The following ancillary work will be required as part of this project: A 600 LF extension of the 10-inch FM from City of Hampton PS 003; A 1,000 LF relocation of the 4-inch FM from the privately owned Hampton Harbor PS; Conveyance of Hampton University PS (Sta. #211) to Hampton University or the Veteran Affairs Medical Center.

PROJECT JUSTIFICATION

In combination with CIP BH014210, this project will address critical areas within the City of Hampton with significant wet weather capacity issues as identified in the Hampton Study completed by Brown and Caldwell (BC). The Hampton Study was a collaborative effort between BC, the City of Hampton and HRSD to identify, evaluate, and select the preferred alternatives to address the identified capacity issues. The existing Willard Avenue PS 30-inch discharge FM was originally installed in the 1945-46 timeframe, with a portion of the main relocated in 1956 as part of the Interstate-64 (I-64) project. Given the age of this line, the documented failure near the I-64 sound wall, limited diversion options, its depth in the vicinity of the interstate off ramp, and Hampton University's request for HRSD to abandon this pipe, replacement is necessary.

FUNDING TYPE

Funding Type: VCWRLF

CONTACTS


Contacts-Requesting Dept: Operations-Interceptors
Contacts-Dept Contacts: Ted Denny
Contacts-Managing Dept: Engineering

PROPOSED SCHEDULE START DATE

PrePlanning	05/01/2015
PER	01/11/2016
Design Delay	05/31/2018
Design	06/26/2018
Bid Delay	11/05/2021
PreConstruction	11/12/2021
Construction	01/01/2022
Closeout	11/01/2025

COST ESTIMATE

Cost Estimate Class:	Class 1 (-3% to +15%)
PrePlanning	\$1,462
PER	\$85,020
Design	\$1,000,131
PreConstruction	\$29,242
Construction	\$15,864,583
Closeout	\$15,000
Est. Program Cost	\$16,995,438
Contingency Budget	\$400,000
Est. Project Costs	\$17,395,438



- BH014900**
- Project Interceptor Line
 - Project Interceptor Point
 - Project Location Point
 - Project Area
- Legend**
- CIP Interceptor Point
 - CIP Pump Station Point
 - CIP Interceptor Line
 - CIP Abandonment
 - CIP Project Area
 - HRSD Interceptor Force Main
 - HRSD Interceptor Gravity Main
 - HRSD Treatment Plant
 - HRSD Pressure Reducing Station
 - HRSD Pump Station

0 137.5 275 550 825 1,100 Feet

BH014900

Hampton Trunk Sewer Extension Division K Gravity Improvements



CIP Location





System: Boat Harbor
Type: Pipelines

Driver Category: I&I Abatement-Rehabilitation Plan
Project Phase: Construction
Regulatory: Rehab Plan Phase Two

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$3,507	\$3,495	\$13	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

PROJECT DESCRIPTION

This project is to rehabilitate and/or replace 3,700 linear feet of 30-inch diameter gravity pipeline with associated manholes. Project extends from MH-NG-160-25773 to NS-PS-225-1. In addition, a point repair is required between MH-NG-160-26350 and MH-NG-160-26040.

PROJECT JUSTIFICATION

Condition assessment activities indicate that these assets present a material risk of failure due to I/I.

FUNDING TYPE

Funding Type: VCWRLF

CONTACTS

Contacts-Requesting Dept: Operations-Interceptors
Contacts-Dept Contacts: Ted Denny
Contacts-Managing Dept: Engineering

PROPOSED SCHEDULE START DATE

PrePlanning	04/01/2019
PER	04/29/2019
Design Delay	05/01/2020
Design	05/01/2020
Bid Delay	02/25/2022
PreConstruction	02/25/2022
Construction	05/01/2022
Closeout	05/01/2025

COST ESTIMATE

Cost Estimate Class:	Class 1 (-3% to +15%)
PrePlanning	\$0
PER	\$106,419
Design	\$285,731
PreConstruction	\$0
Construction	\$3,100,000
Closeout	\$15,000
Est. Program Cost	\$3,507,150
Contingency Budget	\$100,000
Est. Project Costs	\$3,607,150



BH015700

- Project Interceptor Line
- Project Interceptor Point
- Project Location Point
- Project Area

Legend

- ★ CIP Interceptor Point
- ☆ CIP Pump Station Point
- CIP Interceptor Line
- CIP Abandonment
- CIP Project Area
- HRSD Interceptor Force Main
- HRSD Interceptor Gravity Main
- WTP HRSD Treatment Plant
- PRS HRSD Pressure Reducing Station
- PS HRSD Pump Station

0 55 110 220 330 440 Feet

BH015700

Boat Harbor Treatment Plant Pump Station Conversion

CIP Location

System: Boat Harbor
Type: SWIFT

Driver Category: Nutrient Reduction
Project Phase: Construction
Regulatory: Integrated Plan-SWIFT

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$194,418	\$133,807	\$54,001	\$6,611	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

PROJECT DESCRIPTION

The Boat Harbor Treatment Plant will be converted to a pumping station, including equalization and headworks facilities while remaining in operation for wastewater treatment during conversion. The new infrastructure will be designed to meet HRSDs resiliency standards and consider remote operation and access in future conditions including sea level rise.

PROJECT JUSTIFICATION

The James River Waste Load Allocation (WLA) requires HRSD to continue reducing the mass of nutrients discharged from associated treatment plant outfalls. The planned reduction of nutrients is largely completed through implementation of the SWIFT program. The SWIFT master planning effort has determined that advanced water treatment and injection at Boat Harbor has significant physical limitations including site availability and resiliency to sea level rise. In addition, a financial analysis indicates there is significant long term cost savings associated with consolidating wastewater treatment and SWIFT facilities at Nansemond Treatment Plant. This project will allow HRSD to further reduce the amount of nutrients contributed to the James River basin. Upgrades to Nansemond Treatment Plant to accommodate the additional flow will be completed under a separate capital project.

FUNDING TYPE

Funding Type: WIFIA

CONTACTS

Contacts-Requesting Dept: Engineering
Contacts-Dept Contacts: David Steele
Contacts-Managing Dept: Engineering

PROPOSED SCHEDULE START DATE

PrePlanning	08/05/2020
PER	10/27/2020
Design Delay	
Design	08/05/2021
Bid Delay	
PreConstruction	12/21/2022
Construction	05/24/2023
Closeout	12/31/2026

COST ESTIMATE

Cost Estimate Class:	Class 1 (-3% to +15%)
PrePlanning	\$874,598
PER	\$1,134,658
Design	\$4,673,915
PreConstruction	\$139,568
Construction	\$187,560,000
Closeout	\$35,594
Est. Program Cost	\$194,418,334
Contingency Budget	\$4,774,264
Est. Project Costs	\$199,192,598



BH015710

- Project Interceptor Line
- Project Interceptor Point
- Project Location Point
- Project Area

Legend

- ★ CIP Interceptor Point
- ☆ CIP Pump Station Point
- CIP Interceptor Line
- CIP Abandonment
- CIP Project Area
- HRSD Interceptor Force Main
- HRSD Interceptor Gravity Main
- WTP HRSD Treatment Plant
- PRS HRSD Pressure Reducing Station
- PS HRSD Pump Station

0 1,000 2,000 4,000 6,000 8,000 Feet

BH015710

Boat Harbor Treatment Plant Transmission Force Main Section 1 (Subaqueous)

HRSD

N
W E
S

CIP Location



Boat Harbor Treatment Plant Transmission Force Main Section 1 (Subaqueous)

PR_BH015710

System: Boat Harbor
Type: SWIFT

Driver Category: Nutrient Reduction
Project Phase: Construction
Regulatory: Integrated Plan-SWIFT

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$149,143	\$132,816	\$16,327	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

PROJECT DESCRIPTION

The project consists of the subaqueous crossing of the James River to convey flow to the Nansemond Treatment Plant. This project is anticipated to be delivered by the design-build procurement method due to the unique construction techniques required and coordination of construction schedule and permit requirements.

PROJECT JUSTIFICATION

The James River Waste Load Allocation (WLA) requires HRSD to continue reducing the mass of nutrients discharged from associated treatment plant outfalls. The planned reduction of nutrients is largely completed through implementation of the SWIFT program. The SWIFT master planning effort has determined that advanced water treatment and injection at Boat Harbor has significant physical limitations including site availability and resiliency to sea level rise. In addition, a financial analysis indicates there is significant long term cost savings associated with consolidating wastewater treatment and SWIFT facilities at Nansemond Treatment Plant. This project will allow HRSD to further reduce the amount of nutrients contributed to the James River basin. Upgrades to Nansemond Treatment Plant to accommodate the additional flow will be completed under a separate capital project.

FUNDING TYPE

Funding Type: WIFIA

CONTACTS

Contacts-Requesting Dept: Engineering
Contacts-Dept Contacts: David Steele
Contacts-Managing Dept: Engineering

PROPOSED SCHEDULE START DATE

PrePlanning	05/01/2020
PER	10/26/2020
Design Delay	05/05/2022
Design	05/05/2022
Bid Delay	08/10/2021
PreConstruction	05/03/2021
Construction	05/23/2023
Closeout	08/01/2025

COST ESTIMATE

Cost Estimate Class:	Class 1 (-3% to +15%)
PrePlanning	\$0
PER	\$1,237,536
Design	\$8,215,283
PreConstruction	\$467,931
Construction	\$139,222,000
Closeout	\$0
Est. Program Cost	\$149,142,751
Contingency Budget	\$19,580,178
Est. Project Costs	\$168,722,928



BH015720

- Project Interceptor Line
- Project Interceptor Point
- Project Location Point
- Project Area

Legend

- CIP Interceptor Point
- CIP Pump Station Point
- CIP Interceptor Line
- CIP Abandonment
- CIP Project Area
- HRSD Interceptor Force Main
- HRSD Interceptor Gravity Main
- HRSD Treatment Plant
- HRSD Pressure Reducing Station
- HRSD Pump Station

0 220 440 880 1,320 1,760 Feet

BH015720

**Boat Harbor Treatment Plant Transmission Force
Main Section 2 (Land)**



CIP Location





Boat Harbor Treatment Plant Transmission Force Main
Section 2 (Land)

PR_BH015720

System: Boat Harbor
Type: SWIFT

Driver Category: Nutrient Reduction
Project Phase: Construction
Regulatory: Integrated Plan-SWIFT

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$55,301	\$23,569	\$29,807	\$1,925	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

PROJECT DESCRIPTION

This project consists of the on-land transmission force main section connecting the subaqueous force main Section 1 (separate project under BH015710) to the Nansemond Treatment Plant. This project will provide an interceptor force main to be installed using both open cut methods and a trenchless crossing of I-664. HRSD desires to construct this section of force main separate from Section 1 to accommodate coordination with on-going and proposed development of the multiple privately-owned properties that will be traversed. This project includes the SWIFT Water and backflush piping from the future Nansemond SWIFT Facility to each of the proposed well sites located west of I-664.

PROJECT JUSTIFICATION

The James River Waste Load Allocation (WLA) requires HRSD to continue reducing the mass of nutrients discharged from associated treatment plant outfalls. The planned reduction of nutrients is largely completed through implementation of the SWIFT program. The SWIFT master planning effort has determined that advanced water treatment and injection at Boat Harbor has significant physical limitations including site availability and resiliency to sea level rise. In addition, a financial analysis indicates there is significant long term cost savings associated with consolidating wastewater treatment and SWIFT facilities at Nansemond Treatment Plant. This project will allow HRSD to further reduce the amount of nutrients contributed to the James River basin. Upgrades to Nansemond Treatment Plant to accommodate the additional flow will be completed under a separate capital project.

FUNDING TYPE

Funding Type: WIFIA

CONTACTS


Contacts-Requesting Dept: Engineering
Contacts-Dept Contacts: David Steele
Contacts-Managing Dept: Engineering

PROPOSED SCHEDULE START DATE

PrePlanning	05/01/2020
PER	09/29/2021
Design Delay	09/29/2021
Design	12/15/2021
Bid Delay	06/10/2024
PreConstruction	02/29/2024
Construction	05/07/2024
Closeout	08/06/2026

COST ESTIMATE

Cost Estimate Class:	Class 1 (-3% to +15%)
PrePlanning	\$1,438
PER	\$442,502
Design	\$2,441,657
PreConstruction	\$38,284
Construction	\$52,377,000
Closeout	\$0
Est. Program Cost	\$55,300,882
Contingency Budget	\$2,585,260
Est. Project Costs	\$57,886,142



BH015730

- Project Interceptor Line
- Project Interceptor Point
- Project Location Point
- Project Area

Legend

- CIP Interceptor Point
- CIP Pump Station Point
- CIP Interceptor Line
- CIP Abandonment
- CIP Project Area
- HRSD Interceptor Force Main
- HRSD Interceptor Gravity Main
- HRSD Treatment Plant
- HRSD Pressure Reducing Station
- HRSD Pump Station

0 25 50 100 150 200 Feet

BH015730

Boat Harbor Treatment Plant Decommission and Demolition



CIP Location





Boat Harbor Treatment Plant Decommission and Demolition

PR_BH015730

System: Boat Harbor
Type: SWIFT

Driver Category: I&I Abatement-IP/RWWMP
Project Phase: Proposed
Regulatory: Integrated Plan-SWIFT

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$43,001	\$1,049	\$2,894	\$11,125	\$27,932	\$0	\$0	\$0	\$0	\$0	\$0	\$0

PROJECT DESCRIPTION

Boat Harbor Treatment Plant will be converted to a pumping station under a separate capital project. Once wastewater collected from the Boat Harbor service area is diverted to the new Boat Harbor pump station, the treatment plant will be shut down, decommissioned, and demolished, as needed for a potential future land use.

PROJECT JUSTIFICATION

Continued operation of the Boat Harbor Treatment Plant presents challenges to HRSD, including vulnerability to flooding and limited site availability for required wastewater nutrient reduction improvements and SWIFT facilities. HRSD evaluated multiple options to overcome these challenges and found diversion to the Nansemond Treatment Plant provides the most resilient and economical solution to meet HRSD's goals.

FUNDING TYPE

Funding Type: WIFIA

CONTACTS

Contacts-Requesting Dept: Engineering
Contacts-Dept Contacts: David Steele
Contacts-Managing Dept: Engineering

PROPOSED SCHEDULE START DATE

PrePlanning	01/02/2025
PER	01/02/2025
Design Delay	
Design	06/03/2025
Bid Delay	06/15/2026
PreConstruction	06/15/2026
Construction	01/06/2027
Closeout	01/20/2028

COST ESTIMATE

Cost Estimate Class:	Class 5 (-20% to +100%)
PrePlanning	\$0
PER	\$787,000
Design	\$3,147,000
PreConstruction	\$67,000
Construction	\$39,000,000
Closeout	\$0
Est. Program Cost	\$43,001,000
Contingency Budget	\$8,600,000
Est. Project Costs	\$51,601,000



BH015802

-  Project Interceptor Line
-  Project Interceptor Point
-  Project Location Point
-  Project Area

Legend

-  CIP Interceptor Point
-  CIP Pump Station Point
-  CIP Interceptor Line
-  CIP Abandonment
-  CIP Project Area
-  HRSD Interceptor Force Main
-  HRSD Interceptor Gravity Main
-  HRSD Treatment Plant
-  HRSD Pressure Reducing Station
-  HRSD Pump Station

0 25 50 100 150 200 Feet

BH015802

Claremont Pump Station Upgrade (BH-HPP-01B)



CIP Location



System: Boat Harbor
Type: Pump Stations

Driver Category: I&I Abatement-IP/RWWMP
Project Phase: Proposed
Regulatory: Integrated Plan-HPP 2

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$1,295	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$236	\$495	\$565

PROJECT DESCRIPTION

Claremont Pump Station Upgrade (NS-PS-208).

PROJECT JUSTIFICATION

As part of the RWWMP submitted to the DEQ and EPA, HRSD developed an approach to recognize the highest-priority system improvements with the greatest relative environmental benefit. The result being the identification of High-Priority Projects (HPPs). Rounds 1 and 2 of High-Priority Projects were scheduled with consecutive 10-year implementation periods starting with Round 1 being completed between plan approval and 2030. Prior to commencement, HRSD will review the Round 2 projects to confirm that they are still expected to meet the desired result and confirm this in a check in with the EPA/DEQ. To modify the list of specific Round 2 HPP projects, HRSD will show that the revised set of projects will attain a minimum of the same percent reduction, or better.

FUNDING TYPE

Funding Type: Revenue Bond

CONTACTS


Contacts-Requesting Dept: Engineering
Contacts-Dept Contacts: John Dano
Contacts-Managing Dept: Engineering

PROPOSED SCHEDULE START DATE

PrePlanning	01/03/2028
PER	11/01/2032
Design Delay	11/01/2033
Design	11/01/2033
Bid Delay	11/01/2035
PreConstruction	11/01/2035
Construction	01/02/2036
Closeout	01/03/2039

COST ESTIMATE

Cost Estimate Class:	Class 10
PrePlanning	\$0
PER	\$353,313
Design	\$1,130,528
PreConstruction	\$212,013
Construction	\$12,118,622
Closeout	\$0
Est. Program Cost	\$13,814,477
Contingency Budget	\$3,029,655
Est. Project Costs	\$16,844,131



BH015803

- Project Interceptor Line
- Project Interceptor Point
- Project Location Point
- Project Area

Legend

- ★ CIP Interceptor Point
- ☆ CIP Pump Station Point
- CIP Interceptor Line
- CIP Abandonment
- CIP Project Area
- HRSD Interceptor Force Main
- HRSD Interceptor Gravity Main
- WTP HRSD Treatment Plant
- PRS HRSD Pressure Reducing Station
- PS HRSD Pump Station

0 387.5 775 1,550 2,325 3,100 Feet

BH015803

Chesapeake Avenue Interceptor Improvements (BH-01C)

HRSD

N
W E
S

CIP Location



System: Boat Harbor
Type: Pipelines

Driver Category: I&I Abatement-IP/RWWMP
Project Phase: Proposed
Regulatory: Integrated Plan-HPP 2

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$1,739	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$371	\$658	\$710

PROJECT DESCRIPTION

Upgrade 6,490 linear feet (LF) to 42-inch gravity main (GM); Upgrade 2,180 LF of 24-inch GM to 36-inch GM; Upgrade 70 LF of 42-inch inverted siphon along Chesapeake Avenue upstream of NS-PS-208; Upgrade 70 LF of 42-inch inverted siphon along Chesapeake Avenue upstream of NS-PS-208.

PROJECT JUSTIFICATION

As part of the RWWMP submitted to the DEQ and EPA, HRSD developed an approach to recognize the highest-priority system improvements with the greatest relative environmental benefit. The result being the identification of High-Priority Projects (HPPs). Rounds 1 and 2 of High-Priority Projects were scheduled with consecutive 10-year implementation periods starting with Round 1 being completed between plan approval and 2030. Prior to commencement, HRSD will review the Round 2 projects to confirm that they are still expected to meet the desired result and confirm this in a check in with the EPA/DEQ. To modify the list of specific Round 2 HPP projects, HRSD will show that the revised set of projects will attain a minimum of the same percent reduction, or better.

FUNDING TYPE

Funding Type: Revenue Bond

CONTACTS


Contacts-Requesting Dept: Engineering
Contacts-Dept Contacts: John Dano
Contacts-Managing Dept: Engineering

PROPOSED SCHEDULE START DATE


PrePlanning	01/03/2028
PER	11/01/2032
Design Delay	11/01/2033
Design	11/01/2033
Bid Delay	11/01/2035
PreConstruction	11/01/2035
Construction	01/02/2036
Closeout	01/03/2039

COST ESTIMATE

Cost Estimate Class:	Class 10
PrePlanning	\$0
PER	\$556,071
Design	\$1,419,427
PreConstruction	\$314,357
Construction	\$16,371,763
Closeout	\$0
Est. Program Cost	\$18,661,619
Contingency Budget	\$4,092,940
Est. Project Costs	\$22,754,559



- BH016100**
- Project Interceptor Line
 - Project Interceptor Point
 - Project Location Point
 - Project Area
- Legend**
- CIP Interceptor Point
 - CIP Pump Station Point
 - CIP Interceptor Line
 - CIP Abandonment
 - CIP Project Area
 - HRSD Interceptor Force Main
 - HRSD Interceptor Gravity Main
 - HRSD Treatment Plant
 - HRSD Pressure Reducing Station
 - HRSD Pump Station



BH016100

High Priority Projects Round 2 Project 3



CIP Location



System: Boat Harbor
Type: Pipelines

Driver Category: I&I Abatement-IP/RWWMP
Project Phase: Proposed
Regulatory: Integrated Plan-HPP 2

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$18,455	\$0	\$0	\$0	\$0	\$0	\$0	\$436	\$1,307	\$1,851	\$5,607	\$9,255

PROJECT DESCRIPTION

High Priority Project (HPP) Round 2 Project 3 consists of the following Regional Wet Weather Management Plan (RWWMP) Project IDs and general descriptions:
BH-RWWMP-04 58th Street Storage Tank
BH-RWWMP-07 Newmarket Creek Pump Station Upgrade
BH-RWWMP-08 Mercury Boulevard and Newmarket Gravity Main Improvements

PROJECT JUSTIFICATION

As part of the RWWMP submitted to the DEQ and EPA, HRSD developed an approach to recognize the highest-priority system improvements with the greatest relative environmental benefit. The result being the identification of High-Priority Projects (HPPs). Rounds 1 and 2 of High-Priority Projects were scheduled with consecutive 10-year implementation periods starting with Round 1 being completed between plan approval and 2030. Prior to commencement, HRSD will review the Round 2 projects to confirm that they are still expected to meet the desired result and confirm this in a check in with the EPA/DEQ. To modify the list of specific Round 2 HPP projects, HRSD will show that the revised set of projects will attain a minimum of the same percent reduction, or better.

FUNDING TYPE

Funding Type: Revenue Bond

CONTACTS

Contacts-Requesting Dept: Engineering
Contacts-Dept Contacts: John Dano
Contacts-Managing Dept: Engineering

PROPOSED SCHEDULE START DATE

PrePlanning	11/01/2030
PER	11/04/2031
Design Delay	11/03/2032
Design	11/03/2032
Bid Delay	11/02/2033
PreConstruction	11/02/2033
Construction	01/02/2034
Closeout	01/02/2037

COST ESTIMATE

Cost Estimate Class:	Class 10
PrePlanning	\$653,282
PER	\$1,633,206
Design	\$1,959,848
PreConstruction	\$326,641
Construction	\$27,764,510
Closeout	\$326,641
Est. Program Cost	\$32,664,129
Contingency Budget	\$0
Est. Project Costs	\$32,664,129

System: Boat Harbor
Type: Locality and Private Property

Driver Category: I&I Abatement-IP/RWWMP
Project Phase: PER
Regulatory: None

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$10,380	\$983	\$2,290	\$2,919	\$2,919	\$1,247	\$22	\$0	\$0	\$0	\$0	\$0

PROJECT DESCRIPTION

This project includes the identification and reduction of points of inflow into locality and HRSD owned sanitary sewer systems within the Boat Harbor service area. Identification may include data analysis, smoke testing, flow and conductivity monitoring and other field investigations. Inflow reduction strategies may include sealing of manholes, elimination of direct connections, as well as, sealing and replacement of laterals and cleanouts. The Regional Wet Weather Management Plan (RWWMP) has identified basins in current need of inflow reductions and areas of saltwater inflow have been identified through data analysis. Areas to implement inflow reduction strategies will be targeted based on susceptibility to saltwater inflow and through further data analysis of the basins identified in RWWMP. HRSD will coordinate identification and reduction of inflow with locality partners. This project will benefit from the piloted strategies and analysis performed in Phase I.

PROJECT JUSTIFICATION

Hydrographs, flow monitoring, and conductivity monitoring indicate that rapid increases in flow occur during wet weather and high tide events. The rapid inflow of water into the system increases the risk of overflows due to limited hydraulic capacity and increases the risk of force main failures due to increased force main operating pressures. Peak flow reduction in the Boat Harbor service area is desirable to mitigate sanitary sewer overflow (SSO) risk. In addition, reduction of saltwater inflow will protect downstream SWIFT operations.

FUNDING TYPE

Funding Type: Cash

CONTACTS


Contacts-Requesting Dept: Engineering
Contacts-Dept Contacts: Shirley Smith
Contacts-Managing Dept: Engineering

PROPOSED SCHEDULE START DATE

PrePlanning	04/03/2023
PER	12/01/2023
Design Delay	04/01/2025
Design	04/01/2025
Bid Delay	08/01/2025
PreConstruction	08/01/2025
Construction	11/01/2025
Closeout	12/01/2028

COST ESTIMATE

Cost Estimate Class:	Class 5 (-20% to +100%)
PrePlanning	\$3,201
PER	\$582,000
Design	\$530,000
PreConstruction	\$212,000
Construction	\$9,000,000
Closeout	\$53,000
Est. Program Cost	\$10,380,201
Contingency Budget	\$223,000
Est. Project Costs	\$10,603,201



BH016300

-  Project Interceptor Line
-  Project Interceptor Point
-  Project Location Point
-  Project Area

Legend

-  CIP Interceptor Point
-  CIP Pump Station Point
-  CIP Interceptor Line
-  CIP Abandonment
-  CIP Project Area
-  HRSD Interceptor Force Main
-  HRSD Interceptor Gravity Main
-  HRSD Treatment Plant
-  HRSD Pressure Reducing Station
-  HRSD Pump Station

0 25 50 100 150 200 Feet

BH016300

Bayshore Pump Station Replacement



CIP Location



System: Boat Harbor
Type: Pump Stations

Driver Category: Capacity Improvements
Project Phase: Proposed
Regulatory: None

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$14,206	\$0	\$0	\$0	\$0	\$0	\$0	\$322	\$874	\$6,505	\$6,505	\$0

PROJECT DESCRIPTION

This project includes the replacement of the Bayshore Pump Station (PS) to address hydraulic and age-related conditional issues. The proposed replacement will include a relocated pump station and new gravity and force main connections to the existing systems.

PROJECT JUSTIFICATION

Bayshore Pump Station was constructed in 1944. During moderate wet weather events, the station has experienced capacity issues resulting in numerous Sanitary Sewer Overflows (SSO). Over the past decade, this pump station has averaged one SSO per calendar year. In 2021, North Shore Interceptors installed an interim pump to provide additional hydraulic capacity for the station but SSOs still occur as this is not a permanent solution. The pumping configuration of this pump station is also limiting. With only one small pump and two larger pumps, the smaller pump is in operation the vast majority of the time for dry weather flows with no redundancy, and the two larger pumps only run during wet weather events. Due to this configuration, the firm capacity of this station is limited to just one of the larger pumps and is not sufficient for influent flows. In almost all wet weather events, both pumps run at full speed and again have no redundancy. In 2013, an electrical upgrade moved the generator to the exterior of the building. The elevated platform for this generator, combined with the permanently mounted external interim pump, has created an eye sore for the community. The station is near the City of Hampton's Buckroe Beach, and the densely populated neighboring parcels and adjacent community are adversely affected by these structures. Historically, there have been other age-related issues, including an electrical fire in 2008 where one of the internal breaker panels was completely lost.

FUNDING TYPE

Funding Type: Revenue Bond

CONTACTS


Contacts-Requesting Dept: Operations-Interceptors
Contacts-Dept Contacts: Michael Johnson
Contacts-Managing Dept: Operations-Interceptors

PROPOSED SCHEDULE START DATE

PrePlanning	07/01/2030
PER	11/04/2030
Design Delay	07/02/2031
Design	07/02/2031
Bid Delay	07/02/2032
PreConstruction	07/02/2032
Construction	09/02/2032
Closeout	05/02/2034

COST ESTIMATE

Cost Estimate Class: Class 5 (-20% to +100%)	
PrePlanning	\$0
PER	\$322,400
Design	\$873,600
PreConstruction	\$5,200
Construction	\$13,000,000
Closeout	\$5,200
Est. Program Cost	\$14,206,400
Contingency Budget	\$2,433,600
Est. Project Costs	\$16,640,000



- BH016400**
- Project Interceptor Line
 - Project Interceptor Point
 - Project Location Point
 - Project Area
- Legend**
- CIP Interceptor Point
 - CIP Pump Station Point
 - CIP Interceptor Line
 - CIP Abandonment
 - CIP Project Area
 - HRSD Interceptor Force Main
 - HRSD Interceptor Gravity Main
 - HRSD Treatment Plant
 - HRSD Pressure Reducing Station
 - HRSD Pump Station

0 25 50 100 150 200 Feet

BH016400

Jefferson Avenue Pump Station Electrical Improvements



CIP Location



System: Boat Harbor
Type: Electrical

Driver Category: I&I Abatement-IP/RWWMP
Project Phase: Proposed
Regulatory: None

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$920	\$0	\$200	\$720	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

PROJECT DESCRIPTION

This project will design and install a new standby generator, automatic transfer switch (ATS), independent utility service, and motor control center (MCC) at the Jefferson Avenue Pump Station. This equipment is required to ensure continuity of service at the pump station due to the planned decommissioning of the Boat Harbor Treatment Plant.

PROJECT JUSTIFICATION

This project will ensure continuity of service at Jefferson Avenue Pump Station, prior to the decommissioning of Boat Harbor Treatment Plant. The pump station currently receives utility and emergency back-up power from the 13.8 kV Medium Voltage utility switchgear (i.e. electrical distribution system) at Boat Harbor Treatment Plant, which will be disconnected in December 2026 and reconfigured for the full-scale SWIFT facility at Nansemond Treatment Plant. This project will include the installation of underground cabling, conduit, and transformer for the new Dominion Energy utility service. In addition, the project will also include installation of a new standby generator, automatic transfer switch (ATS), motor control center (MCC), and associated electrical equipment.

FUNDING TYPE

Funding Type: Revenue Bond

CONTACTS

Contacts-Requesting Dept: Operations-E&I
Contacts-Dept Contacts: Charles Wright
Contacts-Managing Dept: Engineering

PROPOSED SCHEDULE START DATE

PrePlanning	06/01/2025
PER	06/01/2025
Design Delay	06/01/2025
Design	07/01/2025
Bid Delay	06/01/2026
PreConstruction	06/01/2026
Construction	09/01/2026
Closeout	10/01/2026

COST ESTIMATE

Cost Estimate Class:	Class 5 (-20% to +100%)
PrePlanning	\$0
PER	\$0
Design	\$200,000
PreConstruction	\$0
Construction	\$720,000
Closeout	\$0
Est. Program Cost	\$920,000
Contingency Budget	\$46,000
Est. Project Costs	\$966,000