

York River Treatment Plant







PS HRSD Pump Station





York River Treatment Plant Service Area CIP Projects

Treatment Plant Projects

YR014900 YR015400









Project Interceptor Point

Project Location Point

Project Area

Legend

★ CIP Interceptor Point

☆ CIP Pump Station Point

CIP Interceptor Line

III CIP Abandonment

CIP Project Area

HRSD Interceptor Force Main

HRSD Interceptor Gravity Main

WTP HRSD Treatment Plant

PRS HRSD Pressure Reducing Station

PS HRSD Pump Station

0 275 550 1,100 1,650 2,200

YR010520

Magruder Mercury Interceptor Force Main Replacement - Section B





CIP Location





Magruder Mercury Interceptor Force Main Replacement-Section B

PR_YR010520

System: York River Type: Pipelines Driver Category: Aging Infrastructure/Rehabilitation

Project Phase: Design Regulatory: None

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$19,362	\$1,432	\$9,496	\$8,427	\$7	\$0	\$0	\$0	\$0	\$0	\$0	\$0

PROJECT DESCRIPTION

This project will consist of design and construction for the replacement of the Langley Circle Pump Station yard piping and the targeted replacement of approximately 3,800 linear feet (LF) of the 6,200 LF of 30-inch prestressed concrete cylinder pipe (PCCP) and ductile iron (DI) force main (NF-058) from the Langley Circle Pump Station to just east of the Newmarket Creek Crossing in Hampton identified in the Preliminary Engineering Report as high-risk segments. The target replacement will start at the intersection of North Seldendale Drive and Doolittle Road to a downstream connection location near Air Power Park, located on W. Mercury Boulevard. This project will require bypass pumping and temporary piping to facilitate maintenance of existing flows during construction.

PROJECT JUSTIFICATION

There are a number of infrastructure issues providing the justification for this project and each one will be addressed during the design of the replacement. A force main break and emergency repair occurred on this line in the vicinity of Langley Circle Pump Station due to crown corrosion, and condition assessment efforts performed during the preliminary engineering phase identified which portions of the force main were installed in corrosive soils with no existing corrosion protection and elevated risk of internal crown corrosion.

FUNDING TYPE	CONTACTS


Funding Type: Revenue Bond Contacts-Requesting Dept: Operations-Interceptors

Contacts-Dept Contacts: Beatriz Patino Contacts-Managing Dept: Engineering

COST ESTIMATE

PROPOSED SCHEDULE START DATE

PrePlanning	07/01/2019	Cost Estimate Class:	Class 2 (-5% to +20%)
PER	12/16/2020	PrePlanning	\$61,785
Design Delay	10/08/2021	PER	\$243,373
Design	02/01/2022	Design	\$1,126,922
Bid Delay	07/01/2025	PreConstruction	\$20,000
PreConstruction	08/01/2025	Construction	\$17,900,000
Construction	10/01/2025	Closeout	\$10,000
Closeout	03/01/2027	Est. Program Cost	\$19,362,080
		Contingency Budget	\$1,936,208
		Est. Project Costs	\$21,298,288





Project Interceptor Point

Project Location Point

Project Area

Legend

* CIP Interceptor Point

☆ CIP Pump Station Point

CIP Interceptor Line

CIP Abandonment

CIP Project Area


HRSD Interceptor Force Main

HRSD Interceptor Gravity Main

WTP HRSD Treatment Plant

RSD Pressure Reducing Station

PS HRSD Pump Station



YR010530

Magruder Mercury Interceptor Force Main Replacement - Section C









Magruder Mercury Interceptor Force Main Replacement-Section C

PR_YR010530

System: York River Type: Pipelines Driver Category: Aging Infrastructure/Rehabilitation

Project Phase: Proposed Regulatory: None

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$17,270	\$0	\$0	\$0	\$0	\$250	\$1,000	\$7,353	\$8,000	\$667	\$0	\$0

PROJECT DESCRIPTION

This project will consist of design and construction for the replacement of 8,300 linear feet (LF) of 30-inch prestressed concrete cylinder pipe (PCCP) force main (NF-058) from the intersection of Mercury Boulevard and Windsor Drive to just east of the intersection of Executive Drive and Marcella Road. This project will require bypass pumping and temporary piping to facilitate maintenance of existing flows during construction.


PROJECT JUSTIFICATION

There are a number of infrastructure issues providing the justification for this project and each issue should be considered during the design of the replacement. During the by-pass operation required during the VDOT relocation in the late 1980s, significant debris and sedimentation was observed. The as-built profile and the construction methods used during the original installation of this line provide indication that numerous locations of this force main are at elevated risk for internal crown corrosion. Lastly, there are numerous locations where building structures and/or lack of vehicular and equipment access present significant operational response difficulties.

Funding Type: Revenue Bond Contacts-Requesting Dept: Operations-Interceptors

Contacts-Dept Contacts: Chris Stephan Contacts-Managing Dept: Engineering

PrePlanning	09/01/2028	Cost Estimate Class:	Class 5 (-20% to +100%)
PER	10/01/2028	PrePlanning	\$0
Design Delay	12/01/2028	PER	\$250,000
Design	08/01/2029	Design	\$1,000,000
Bid Delay	11/01/2029	PreConstruction	\$20,000
PreConstruction	07/01/2030	Construction	\$16,000,000
Construction	08/01/2030	Closeout	\$0
Closeout	08/01/2032	Est. Program Cost	\$17,270,000
		Contingency Budget	\$1,603,289
		Est. Project Costs	\$18,873,289





Project Interceptor Point

Project Location Point

Project Area

Legend

★ CIP Interceptor Point

☆ CIP Pump Station Point

CIP Interceptor Line

CIP Abandonment

CIP Project Area

HRSD Interceptor Force Main

HRSD Interceptor Gravity Main

WTP HRSD Treatment Plant

HRSD Pressure Reducing Station

S HRSD Pump Station



YR010900

Tabb Pressure Reducing Station and Offline Storage Facility





CIP Location





Tabb Pressure Reducing Station and Offline Storage Facility

PR_YR010900

System: York River
Type: Offline Storage

Driver Category: I&I Abatement-IP/RWWMP

Project Phase: Construction

Regulatory: Integrated Plan-HPP 1

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$40,819	\$26,977	\$13,842	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

PROJECT DESCRIPTION

This project will construct a new Pressure Reducing Station (PRS) and Offline Storage Tank in the vicinity of Tabb High School in York County, Virginia. The precise capacity of the station and volume of the tank will be determined during the preliminary design.

PROJECT JUSTIFICATION

Staff determined the Tabb PRS and Offline Storage Facility project would eliminate the need for an onsite storage vessel at the James River Treatment Plant (JRTP). The facility will provide flow equalization to both York River and James River Treatment plants and also provide system relief during wet weather events.

FUNDING TYPE		CONTACTS
Funding Type:	Revenue Bond	Contacts-Requesting Dept: Operations-Interceptors Contacts-Dept Contacts: Angela Weatherhead Contacts-Managing Dept: Engineering

PrePlanning	02/28/2020	Cost Estimate Class:	Class 1 (-3% to +15%)
PER	06/01/2020	PrePlanning	\$1,229
Design Delay	02/21/2022	PER	\$585,657
Design	02/20/2021	Design	\$3,085,330
Bid Delay	07/05/2023	PreConstruction	\$22,681
PreConstruction	09/18/2023	Construction	\$37,099,267
Construction	01/01/2024	Closeout	\$25,000
Closeout	05/01/2026	Est. Program Cost	\$40,819,164
		Contingency Budget	\$3,406,115
		Est. Project Costs	\$44,225,279





Project Interceptor Point

Project Location Point

Project Area

Legend

★ CIP Interceptor Point

☆ CIP Pump Station Point

CIP Interceptor Line

CIP Abandonment

CIP Project Area


HRSD Interceptor Force Main

HRSD Interceptor Gravity Main

WTP HRSD Treatment Plant

HRSD Pressure Reducing Station

PS HRSD Pump Station



YR011900

Bethel-Poquoson Force Main Part III Replacement







System: York River Type: Pipelines

Driver Category: Relocation
Project Phase: Construction

Regulatory: None

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$1,680	\$889	\$627	\$162	\$2	\$0	\$0	\$0	\$0	\$0	\$0	\$0

PROJECT DESCRIPTION

This work will be constructed as part of a Virginia Department of Transportation (VDOT) roadway improvements project. Portions of the existing pipeline will be relocated at VDOT project expense and some portions will be relocated at HRSD expense. This project will replace and/or rehabilitate approximately 4,400 linear feet of existing 20-inch pre-stressed concrete cylinder pipe (PCCP) along the eastern edge of Wythe Creek Road. VDOT will replace approximately 2,650 feet of pipe at project cost and HRSD will be responsible for replacement of 1,750 feet of pipe at HRSD's cost.


PROJECT JUSTIFICATION

The relocation of this pipeline is due to a VDOT roadway project to widen Wythe Creek Road.

FUNDING TYPE	=	CONTACTS	
Funding Type:	Revenue Bond	Contacts-Requesting Deprocessing Contacts-Dept Contacts: Contacts-Managing Dept:	Shirley Smith
PROPOSED SO	CHEDULE START DATE	COST ESTIMATE	
PrePlanning	01/01/2015	Cost Estimate Class:	Class 1 (-3% to +15%)
PER	01/01/2015	PrePlanning	\$0
Design Delay	01/01/2015	PER	\$0
Design	01/01/2015	Design	\$17,998
Bid Delay	08/21/2020	PreConstruction	\$0
PreConstruction	11/01/2023	Construction	\$1,608,454
Construction	03/01/2024	Closeout	\$7,090
Closeout	10/01/2026	Est. Program Cost	\$1,633,542
		Contingency Budget	\$141,80 <u>0</u>

Est. Project Costs

\$1,775,342





Project Interceptor Point

Project Location Point

Project Area

Legend

* CIP Interceptor Point

☆ CIP Pump Station Point

CIP Interceptor Line

CIP Abandonment

CIP Project Area

HRSD Interceptor Force Main

HRSD Interceptor Gravity Main

WTP HRSD Treatment Plant

RSD Pressure Reducing Station

PS HRSD Pump Station

0 500 1,000 2,000 3,000 4,000

YR013900

York River System Isolation Valve Installation and Replacement









York River System Isolation Valve Installation and Replacement

System: York River Type: Pipelines Driver Category: Aging Infrastructure/Rehabilitation

Project Phase: Closeout Regulatory: None

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$8,993	\$8,883	\$110	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

PROJECT DESCRIPTION

This project will install eight new valves and replace three existing valves. These valves are main line and branch isolation valves within the force main system from Coliseum Pressure Reducing Station (PRS) to the proposed Tabb PRS and will provide operational flexibility for isolation and flow diversion.

PROJECT JUSTIFICATION

On December 20th, 2018, North Shore Operations responded to a failure along NF-047 in the vicinity of Semple Farm Road. Efforts to minimize the effects of environmental and physical damage were extensive. Round the clock operation was necessary to divert flows, minimize spills and restore service. A temporary repair was made to contain lost sewage and pump it back into the force main system. Final repair consisted of an engineer designed replacement of approximately 300 linear feet (LF) of force main utilizing linestops. The existing force main system from Coliseum PRS to Tabb PRS consists of approximately 38,000 LF of force main with very few locations for potential isolation. The force main system was primarily installed in the late 1960's and early 1970's and consists of Prestressed Concrete Cylinder Pipe (PCCP), Ductile Iron (DI) and Cast Iron (CI) pipe. The lack of isolation valves significantly reduces the ability for isolating and diverting flows during emergencies, as seen during the failure at Semple Farm.

FUNDING TYPE CONTACTS


Funding Type: Revenue Bond Contacts-Requesting Dept: Operations-Interceptors

Contacts-Dept Contacts: Michael Johnson Contacts-Managing Dept: Engineering

COST ESTIMATE

PROPOSED SCHEDULE START DATE

PrePlanning	07/01/2019	Cost Estimate Class:	Class 1 (-3% to +15%)
PER	11/28/2019	PrePlanning	\$0
Design Delay	Delay 04/25/2020 PER		\$65,023
Design	04/25/2020	Design	\$344,164
Bid Delay	03/23/2022	PreConstruction	\$9,900
PreConstruction	04/15/2022	Construction	\$8,554,003
Construction	07/14/2022	Closeout	\$20,000
Closeout	08/01/2025	Est. Program Cost	\$8,993,091
		Contingency Budget	\$100,000
		Est. Project Costs	\$9,093,091





☆ CIP Pump Station Point

CIP Interceptor Line

III CIP Abandonment

CIP Project Area


HRSD Interceptor Force Main

HRSD Interceptor Gravity Main

WTP HRSD Treatment Plant

HRSD Pressure Reducing Station

HRSD Pump Station



YR014200

LaSalle Avenue Boat Harbor to York River Interconnect Force Main









LaSalle Avenue Boat Harbor to York River Interconnect Force Main

PR_YR014200

System: York River Type: Pipelines Driver Category: Capacity Improvements

Project Phase: PER Regulatory: None

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$16,943	\$129	\$0	\$0	\$605	\$1,048	\$9,094	\$6,065	\$3	\$0	\$0	\$0

PROJECT DESCRIPTION

This project will involve the study, design and construction of 10,000 linear feet (LF) of 30-inch Interceptor Force Main (IFM) from the intersection of LaSalle Avenue and Victoria Boulevard to the intersection of LaSalle Avenue and Mercury Boulevard. A gravity interconnect will be installed between this new force main (FM) and NG-142 Ivy Home Shell Road Sewer Extension Division I and an interconnect between the proposed FM and the existing NF-77 LaSalle Avenue Sanitary Sewer IFM will allow for system flexibility.

PROJECT JUSTIFICATION

This newly proposed force main interconnect is needed to shift peak flows currently in the Boat Harbor Treatment Plant service area by diverting these flows through the Coliseum Pressure Reducing Station (PRS). With the scheduled future shutdown of the Boat Harbor Treatment Plant, this project will maximize the wet weather capabilities at York River Treatment Plant (YRTP) while minimizing the peak flows within the Boat Harbor system. This project, along with newly proposed storage tanks at Coliseum PRS, will allow for flows from the Bridge Street and Victoria Boulevard Pump Station service areas to be diverted north through the Coliseum PRS.

FUNDING TYPE CONTACTS

Funding Type: Revenue Bond Contacts-Requesting Dept: Operations-Interceptors

Contacts-Dept Contacts: Ted Denny
Contacts-Managing Dept: Engineering

PrePlanning	03/26/2020	Cost Estimate Class:	Class 4 (-15% to +50%)
PER	12/02/2022	PrePlanning	\$1,454
Design Delay	04/02/2025	PER	\$125,580
Design	01/01/2028	Design	\$1,615,000
Bid Delay	05/01/2029	PreConstruction	\$40,000
PreConstruction	05/01/2029	Construction	\$15,156,000
Construction	07/01/2029	Closeout	\$5,100
Closeout	03/01/2031	Est. Program Cost	\$16,943,134
		Contingency Budget	\$2,692,000
		Est. Project Costs	\$19,635,134





Project Interceptor Point

Project Location Point

Project Area

Legend

* CIP Interceptor Point

☆ CIP Pump Station Point

CIP Interceptor Line

CIP Abandonment

CIP Project Area


HRSD Interceptor Force Main

HRSD Interceptor Gravity Main

WTP HRSD Treatment Plant

RSD Pressure Reducing Station

PS HRSD Pump Station



YR014700

Coliseum PRS Off-Line Storage Tank Odor Control Upgrades







Coliseum PRS Off-Line Storage Tank Odor Control Upgrades

PR_YR014700

System: York River
Type: Offline Storage

Driver Category: Performance Upgrades

Project Phase: Construction Regulatory: None

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$575	\$570	\$5	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

PROJECT DESCRIPTION

The project will include the design and construction of an access platform and jib crane for the existing carbon scrubber systems.


PROJECT JUSTIFICATION

The platform and jib crane will provide a much needed improvement to safety and access of the existing carbon units, both for carbon change out operations and for maintenance inspections.

Funding Type: Revenue Bond Contacts-Requesting Dept: Operations-Interceptors

Contacts-Dept Contacts: Ann Copeland Contacts-Managing Dept: Engineering

PrePlanning		Cost Estimate Class:	Class 1 (-3% to +15%)
PER		PrePlanning	\$0
Design Delay		PER	\$39,600
Design	05/23/2022	Design	\$114,451
Bid Delay	11/08/2024	PreConstruction	\$10,185
PreConstruction	11/08/2024	Construction	\$406,000
Construction	12/01/2024	Closeout	\$5,000
Closeout	07/01/2025	Est. Program Cost	\$575,236
		Contingency Budget	\$60,800
		Est. Project Costs	\$636,036





Project Interceptor Point

Project Location Point

Project Area

Legend

★ CIP Interceptor Point

☆ CIP Pump Station Point

CIP Interceptor Line

III CIP Abandonment

CIP Project Area


HRSD Interceptor Force Main

HRSD Interceptor Gravity Main

WTP HRSD Treatment Plant

RSD Pressure Reducing Station

PS HRSD Pump Station



YR014900

York River DEMON Upgrades









Type:

System: York River

Wastewater Treatment

Driver Category: Performance Upgrades

Project Phase: Construction

Regulatory: None

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$551	\$328	\$223	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

PROJECT DESCRIPTION

Currently, the DEMON process is a sequencing batch reactor with anammox granules retained in the system with a screen and partial nitration occurring in the mixed liquor. The goal of this project is to incorporate biofilm carriers for anammox to increase process reliability and stability. HRSD will be evaluating a fixed media option vs moving media in a full-scale demonstration at James River Treatment Plant (JRTP). If fixed-film is successful at JRTP, it would be the preferred option for the York River Treatment Plant DEMON, otherwise the fall back option will be moving media.

PROJECT JUSTIFICATION

The goal is to improve reliability and stability of the process by making it more resistant to upsets from high influent Total Suspended Solids (TSS) by switching from a hybrid granular/suspended growth process to an attached growth process. Currently, there are frequent upsets from influent TSS that cause temporary shutdowns and sometimes restarts which require a significant amount of operator time and attention. When DEMON is offline, the nitrogen loading is increased on the plant which uses more aeration, alkalinity, and methanol.

Funding Type: Revenue Bond Contacts-Requesting Dept: Operations-Treatment

Contacts-Dept Contacts: Mike Parsons

Contacts-Managing Dept: Operations-Treatment

PrePlanning	03/01/2023	Cost Estimate Class:	Class 1 (-3% to +15%)
PER	03/01/2023	PrePlanning	\$0
Design Delay	03/01/2023	PER	\$0
Design	03/01/2023	Design	\$0
Bid Delay	03/01/2023	PreConstruction	\$0
PreConstruction	03/01/2023	Construction	\$551,200
Construction	03/01/2023	Closeout	\$0
Closeout	01/02/2026	Est. Program Cost	\$551,200
		Contingency Budget	\$0
		Est. Project Costs	\$551,200





System:

Type:

York River Treatment Plant Switchgear and Motor Control Center Replacements

York River Driver Category: Aging Infrastructure/Rehabilitation Electrical Project Phase: Proposed

Project Phase: Proposed Regulatory: None

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$14,040	\$0	\$1,525	\$1,620	\$1,469	\$1,469	\$1,469	\$1,469	\$1,469	\$1,469	\$1,469	\$612

PROJECT DESCRIPTION

This project is to replace twelve (12) motor control centers (MCC's). The MCC's were installed in the early 1980's and feed the Digester Building, DAF (Dissolved Activated Flotation) Building, Final Effluent Pump Station, Primary Solids Building, Administration Operations Building, and Odor Control Building. To extend the life of the new Primary MCC and remove the MCC from a harsh environment, the MCC will be relocated from the basement to a prefabricated electrical room that will be receted above ground. In addition, this project will replace 4160V medium voltage switchgear located in the administration building. The new switchgear lineup will provide remote racking and modernize the protective relaying by using solid state relays versus induction disc relays.

PROJECT JUSTIFICATION

This project will replace vintage MCC's that have reached the end of their useful life. The replacement parts are not readily available. The replacement of the MCC's will improve reliability and avert any disruptions to the plant processes. In addition, this project will reduce hazards to employees associated with arc flash.


FUNDING TYPE		CONTACTS	
Funding Type:	Revenue Bond	Contacts-Requesting Dept: Contacts-Dept Contacts: E Contacts-Managing Dept: E	Donald Jennings
PROPOSED SC	HEDULE START DATE	COST ESTIMATE	
PrePlanning	01/01/2025	Cost Estimate Class: CI	ass 5 (-20% to +100%)
PER	08/01/2025	PrePlanning	\$0
Design Delay	02/01/2026	PER	\$0
Design	03/01/2026	Design	\$2,288,000
Bid Delay	09/01/2026	PreConstruction	\$0
PreConstruction	10/01/2026	Construction	\$11,752,000
Construction	12/01/2026	Closeout	<u>\$0</u>
Closeout	12/01/2034	Est. Program Cost	\$14,040,000

Contingency Budget

Est. Project Costs

\$1,404,000

\$15,444,000





Project Interceptor Point

Project Location Point

Project Area

Legend

★ CIP Interceptor Point

☆ CIP Pump Station Point

CIP Interceptor Line

CIP Abandonment

CIP Project Area

HRSD Interceptor Force Main

HRSD Interceptor Gravity Main

WTP HRSD Treatment Plant

PRS HRSD Pressure Reducing Station

PS HRSD Pump Station

	_	_			Feet
0	360	720	1,440	2,160	2,880

YR015200

Bethel-Poquoson and Route 171 Victory Blvd Interceptor Force Main Relocation









Bethel Poquoson and Route 171 Victory Blvd IFM Relocation

PR_YR015200

System: York River Type: Pipelines Driver Category: Aging Infrastructure/Rehabilitation

Project Phase: Proposed Regulatory: None

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$4,168	\$0	\$0	\$0	\$0	\$0	\$0	\$390	\$423	\$2,233	\$1,122	\$0

PROJECT DESCRIPTION

This project is to design and construct a new force main to replace portions of NF-025 & NF-026. The project will include the abandonment of 1,600 linear feet (LF) of 18-inch and 600 LF of 20-inch reinforced concrete cylinder pipe. This scope also consists of replacing two (2) valve complexes, one at Wythe Creek Road and Little Florida Avenue and the other at the intersection of Little Florida Road and Poquoson Avenue.

PROJECT JUSTIFICATION


NF-025 & NF-026 were placed into service in 1970. Both force mains have experienced corrosion-related failures. In 1986, NF-026 experienced its failure, and the pipe failed due to a corrosive attack. In 1997, NF-025 experienced a corrosion-related failure at an unvented high spot. Along with corrosion-related failures, multiple valves on both force mains have failed. Valve YR3017-2, located at Poquoson Avenue and Little Florida intersection, has failed in the open position and leaks if operated. The Wythe Creek Road and Little Florida Avenue valve complex has several valves with operational issues. Valve YR3012-1 failed in the open position, and leaks if operated. Valve YR3012-2 has failed in the open position and is considered inoperable (frozen). In addition to the information above, the force main and valve locations provide operational and access issues. Any failures on this line would create serious impact to residents and emergency services.

Funding Type: Revenue Bond Contacts-Requesting Dept: Operations-Interceptors

Contacts-Dept Contacts: Michael Johnson

Contacts-Managing Dept: Operations-Interceptors

PrePlanning	07/01/2030	Cost Estimate Class:	Class 10
PER	09/01/2030	PrePlanning	\$0
Design Delay	02/01/2031	PER	\$183,000
Design	02/01/2031	Design	\$580,000
Bid Delay	04/01/2032	PreConstruction	\$50,000
PreConstruction	04/01/2032	Construction	\$3,350,000
Construction	07/01/2032	Closeout	\$5,000
Closeout	01/01/2034	Est. Program Cost	\$4,168,000
		Contingency Budget	\$822,600
		Est. Project Costs	\$4,990,600





Project Interceptor Point

Project Location Point

Project Area

Legend

★ CIP Interceptor Point

☆ CIP Pump Station Point

CIP Interceptor Line

CIP Abandonment

CIP Project Area


HRSD Interceptor Force Main

HRSD Interceptor Gravity Main

WTP HRSD Treatment Plant

HRSD Pressure Reducing Station

HRSD Pump Station



YR015300

Wolf Trap Road Interceptor Improvements





CIP Location





System: York River Type: Pipelines Driver Category: Aging Infrastructure/Rehabilitation

Project Phase: Proposed Regulatory: None

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$7,150	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$925	\$2,025	\$4,200	\$0

PROJECT DESCRIPTION

This project is to design and construct a new force main to relocate a portion of NF-010 and NF-011. Along with the segmental relocations, this project will remove and replace several valves that have failed and are on the influent force main to the York River Treatment Plant.

PROJECT JUSTIFICATION

The segmental replacement of NF-010 is to remove the force main installed in the 1970s. The location of the force main presents significant safety risks when performing maintenance due to its placement within a busy traffic lane. Maintenance records for the valves associated with this project indicate several failed valves. In September of 2024, valve YR1005-1 began to leak while operations staff were performing preventative maintenance activities; the estimated leak rate was 10 gallons per minute, and operations staff were able to divert flows and complete the repair to the valve and stop the leak. All flow entering the YRTP passes through this valve, and there is no redundant downstream valve. This valve would be operated if a catastrophic failure occurred at the York River Treatment Plant and flows needed to be diverted to the other plants. Given the critical role of these valves within the interceptor system, it is recommended that they be removed and replaced to improve both safety and system reliability.

FUNDING TYPE	CONTACTS
--------------	----------


Funding Type: Revenue Bond Contacts-Requesting Dept: Operations-Interceptors

Contacts-Dept Contacts: Michael Johnson
Contacts-Managing Dept: Operations-Interceptors

COST ESTIMATE

PROPOSED SCHEDULE START DATE

PrePlanning	07/01/2031	Cost Estimate Class:	Class 10
PER	07/01/2031	PrePlanning	\$0
Design Delay	01/01/2032	PER	\$300,000
Design	01/01/2032	Design	\$1,250,000
Bid Delay	01/01/2033	PreConstruction	\$0
PreConstruction	01/01/2033	Construction	\$5,600,000
Construction	04/01/2033	Closeout	\$0
Closeout	04/01/2034	Est. Program Cost	\$7,150,000
		Contingency Budget	\$1,120,000
		Est. Project Costs	\$8,270,000



YR015400

Project Interceptor Line

Project Interceptor Point

Project Location Point

Project Area

Legend

★ CIP Interceptor Point

☆ CIP Pump Station Point

CIP Interceptor Line

CIP Abandonment

CIP Project Area


HRSD Interceptor Force Main

HRSD Interceptor Gravity Main

WTP HRSD Treatment Plant

RSD Pressure Reducing Station

PS HRSD Pump Station



YR015400

York River Treatment Plant Fire Suppression System Upgrades











Type:

York River Treatment Plant Fire Suppression System Upgrades

System: York River

Wastewater Treatment

Driver Category: Safety Compliance

Project Phase: Proposed Regulatory: None

PROGRAM CASH FLOW PROJECTION (\$,000)

Prog Cost	Exp to Previous Year	FY26	FY27	FY28	FY29	FY30	FY31	FY32	FY33	FY34	FY35
\$3,580	\$0	\$1,602	\$1,971	\$7	\$0	\$0	\$0	\$0	\$0	\$0	\$0

PROJECT DESCRIPTION

This project will address the replacement or upgrades of the fire suppression system at the York River Treatment Plant methanol facility. Currently, the fire suppression system at this plant's methanol facility utilizes an Alcohol Resistant Aqueous Film Forming Foam (AR-AFFF) that contains Perfluoroalkyl and Polyfluoroalkyl (PFAS). Refilling the existing extinguishers with AR-AFFF will no longer be permitted due to the environmental and health concerns associated with PFAS. The new or upgraded systems will utilize a non-PFAS fluorine free foam to extinguish fires.

PROJECT JUSTIFICATION

The current methanol fire suppression systems use AR-AFFF which contains PFAS. AR-AFFF foam is being phased out due to the Federal Forever Chemical Regulation Accountability Act of 2024. If the fire suppression systems is discharged the existing system cannot be re-charged. In the past, some of these fire suppression systems have experienced false alarms and equipment malfunctions causing activation of the AR-AFFF.

CONTACTS
L

Funding Type: Revenue Bond Contacts-Requesting Dept: Operations-Treatment

Contacts-Dept Contacts: Charles Bott Contacts-Managing Dept: Engineering

COST ESTIMATE

PROPOSED SCHEDULE START DATE

PrePlanning 06/01/2025 **Cost Estimate Class:** Class 5 (-20% to +100%) PrePlanning **PER** 06/01/2025 \$0 Design Delay 08/01/2025 PER \$0 08/01/2025 Design \$0 Design 12/01/2025 PreConstruction Bid Delay \$32,400 Construction PreConstruction 12/01/2025 \$3,531,600 Closeout Construction \$16,200 03/01/2026 Est. Program Cost Closeout 12/01/2026 \$3,580,200 Contingency Budget \$895,050 \$4,475,250 **Est. Project Costs**